

# FOURTH AMENDMENT TO BROWARD COUNTY P25 SYSTEM AND SERVICES MASTER AGREEMENT WITH MOTOROLA SOLUTIONS, INC.

This Fourth Amendment ("Fourth Amendment") is entered into by and between Broward County, a political subdivision of the State of Florida ("County"), and Motorola Solutions, Inc., a Delaware corporation ("Motorola Solutions" or "Provider") (collectively County and Provider are referenced as the "Parties").

#### **RECITALS**

- A. The Parties entered into the Broward County P25 System and Services Master Agreement with Motorola Solutions, Inc., dated May 23, 2017 for a new 700 MHz, P25 Phase II system to replace the County's existing 800 MHz SmartNet System, a new IP-based microwave system to replace the existing Tadiran 6 GHz system and providing backward compatibility for legacy circuits, and related civil work, software, equipment, and support and maintenance.
- B. The Parties subsequently entered into a First Amendment, dated June 28, 2018, to, among other things, change the master Site from the Core Site to the Davie Site and add new shelters to multiple Sites; a Second Amendment, dated October 23, 2018, to provide for the purchase of additional Subscriber Equipment by other County agencies; and a Third Amendment, dated November 7, 2018, to provide for the discounted purchase of additional Subscriber Equipment. As amended, the Parties' agreement is referred to herein as the "Agreement."
- C. The Parties desire to further amend the Agreement to, among other things, expand the scope of Equipment supported by Motorola Solutions to include the existing generators at certain Sites, to provide for the purchase of via Work Authorizations of certain additional equipment and services for a security system at the Sites and a microwave system for certain locations for County's Water and Wastewater Services, and to reflect certain modifications in scope at certain Sites and associated pricing.

Now, therefore, for good and valuable consideration, the receipt and adequacy of which are hereby acknowledged, County and Motorola Solutions agree as follows:

- 1. The above Recitals are true and correct and are incorporated herein by reference. All capitalized terms not expressly defined within this Fourth Amendment shall retain the meaning ascribed to such terms in the Agreement.
- 2. Except as modified herein, all terms and conditions of the Agreement remain in full force and effect. Amendments are indicated herein by use of strikethroughs to indicate deletions and bold/underlining to indicate additions.

- 3. Section 1.5 of the Agreement is amended as follows:
  - 1.5 <u>Contract Administrator</u>. The Director of Office of Regional <u>Emergency Services and</u> Communications and <u>Technology</u> or other person as designated in writing by the Director of the Office of Regional <u>Emergency Services and</u> Communications and <u>Technology</u> for all or portions of this Agreement and the Services provided hereunder <u>relating to the P25 System</u>. <u>Solely for the purposes of the Work Authorization for the Microwave System for WWS (to the extent elected by County as Optional Services), the <u>Contract Administrator shall refer to the Director of Broward County's Water and Wastewater Services Division.</u></u>
- 4. Section 3.4 of the Agreement is amended as follows:
  - 3.4 Support and Maintenance Services. For so long as requested by County, Provider shall provide Support and Maintenance Services for the P25 System at the rates set forth in the Payment Schedule to ensure the proper functioning and optimal performance of the P25 System as set forth in the Documentation pursuant to the terms of Exhibit C. For Until completion of the first year following Final Acceptance, all Support and Maintenance Services for the P25 System are included at no additional cost unless otherwise stated in Exhibit B. For subsequent years, Support and Maintenance Services for the applicable System shall be invoiced and paid in accordance with the Payment Schedule set forth in Exhibit B. County may elect to suspend, discontinue, or recommence Support and Maintenance Services for the P25 System or for any or all of the component Systems upon thirty (30) days' prior notice, with the applicable fees prorated for the applicable term, without reinstatement or other penalty.
- 5. Section 4.7 of the Agreement is amended as follows:
  - 4.7 <u>Liquidated Damages</u>. Liquidated damages are hereby fixed and agreed upon between the Parties as set below, recognizing the impossibility of precisely ascertaining the amount of damages that will be sustained by County as a consequence of such delay, and both Parties desiring to obviate any question of dispute concerning the amount of said damages and the cost and effect of the failure of Provider to complete each System, the inability to continue to operate and maintain each Site, and the failure to complete the P25 System on time. These amounts are not penalties but liquidated damages to County for its inability to obtain full beneficial use of the P25 System. For purposes of this paragraph, any delays caused by County prior to Final Acceptance or Final Completion shall extend the deadline for the affected System(s) by the same number of days as the delay caused by County. The liquidated damages stated herein are cumulative, unless waived by County Contract Administrator, and shall be continuing until remedied. The total liquidated damages charged to Provider under this Section 4.7 shall not exceed ten percent (10%) of the System Total as set forth on Exhibit B.

In the event the County Contract Administrator, after consultation with Provider, determines that an unusual circumstance or insurmountable obstacle beyond Provider's reasonable control prohibits timely completion of a portion of the Work and adversely impacts the Project Schedule, Provider and the County Contract Administrator will agree in writing on any extended deadline(s) to the Work impacted, and Schedule 10 and any other impacted deadlines so extended in writing shall be deemed automatically updated. Any such extension requires the written approval of the County Contract Administrator.

The Parties agree that the deadlines referenced in this Section 4.7 were amended by the Fourth Amendment and that some or all of the original deadlines expired prior to the execution of the Fourth Amendment. To the extent any liquidated damages accrued prior to the effective date of the Fourth Amendment, all rights and remedies are reserved.

- 4.7.1. <u>Damages for Failure to Achieve Substantial Completion</u>. Upon failure of Provider to achieve Substantial Completion of any Site within the time periods specified in the applicable Project Schedule (plus approved extensions, if any), Provider shall pay to County liquidated damages in the amount of \$250 for each calendar day after the time specified in the Project Schedule.
- 4.7.2. Operation and Maintenance of Sites During Construction. Upon failure of Provider to meet the operating and maintenance criteria set forth in Exhibit A-2 for any Site, Provider shall pay to County liquidated damages in the amount as stated in Exhibit A-2 (if none stated, then the amount of \$100) for each occurrence or series of occurrences of operating or maintenance failure.
- 4.7.3. <u>Damages for Failure to Milestones or Final Acceptance</u>. If any System fails to achieve the milestones stated below, Provider shall pay to County liquidated damages in the amount of \$2,500 for each calendar day by which the date of the achievement of the applicable milestone exceeds the applicable deadline.
  - 4.7.3.1. Completion of FNE installation at all RF Sites: August 30, 2018

    December 31, 2019.
  - 4.7.3.2. Commencement of 30 Day Operational Test: November 21, 2018

    March 30, 2020.
  - 4.7.3.3. P25 System Final Acceptance: <del>December 31, 2018</del> April 24, 2020.
- 4.7.4. <u>Deduction from Amounts Otherwise Due</u>. County is authorized to deduct any liquidated damages due under this Agreement from monies due Provider for Services or other work under this Agreement or as much thereof as County may, in its sole option and discretion, deem just and reasonable.

- 6. Not-To-Exceed Amounts. Section 5.1 of the Agreement is amended as follows:
  - 5.1 For the duration of the Agreement, County will pay Provider in accordance with the Payment Schedule (Exhibit B) up to the following maximum amount(s):

Services/Goods	Term	Not-To-Exceed Amount
P25 System Implementation	From Effective Date to	<del>\$34,500,000</del>
(including Radio System,	Final Acceptance	<u>\$37,500,000</u>
Microwave System, and		
Facilities and Infrastructure		
System)		
Additional Training	Initial Term (10 years)	\$200,000
Support and Maintenance	Initial Term (10 years)	\$11,000,000
Services		
Optional renewal terms	First 5 year renewal term	\$7,100,000
		(includes \$100,000 for
		additional training)
	Second 5 year renewal	
	term	\$8,300,000
		(includes \$100,000 for
		additional training)
Optional Services (including	Duration of the	<del>\$2,500,000</del>
County purchases of	Agreement (inclusive of	<b>\$3,500,000</b> (any Optional
Subscriber Equipment)	any renewals)	Services)
		\$10,097,000 (County
		purchases of Subscriber
		Equipment)
Microwave System for WWS	<b>Duration of the</b>	<u>\$500,000</u>
(Optional Services)	Agreement (inclusive of	
	any renewals)	
TOTAL NOT TO EXCEED		<del>\$73,697,000</del>
		<u>\$78,197,000</u>

\* \* \*

7. <u>Updated Statement of Work</u>. Exhibit A-2, Facilities and Infrastructure Development, is amended as set forth in Exhibit A-2 hereto (including the entirety of the schematics as Attachment B thereto, which are included in this Fourth Amendment in only excerpted format due to length) in selected portions of Section 2, as well as Section 3 and Section 4. All sections not included in the attached amendment to Exhibit A-2 remain unchanged. The amended portions of Section 2 are as follows:

- a) Section 2.1 (Core Site);
- b) Section 2.2 (Coconut Creek Site);
- c) Section 2.3 (Markham Park Site);
- d) Section 2.5 (Davie Site);
- e) Section 2.7 (Miramar Site);
- f) Section 2.10 (Tamarac Site);
- g) Section 2.12 (Sunrise Dispatch);
- h) Section 2.13 (Coconut Creek Dispatch);
- i) Section 2.14 (Pembroke Pines Dispatch);
- j) Section 2.15 (FS 106 Site);
- k) Section 2.16 (Parkland Site);
- Section 2.17 (West Hollywood Site);
- m) Section 2.18 (Pompano Beach Club Site); and
- n) Section 2.19 (EMS Site).
- 8. <u>Updated Schedules</u>. Schedule 2 (Equipment Schedule) has been updated by agreement of the Parties to incorporate the additional equipment included pursuant to this Fourth Amendment, including Attachment A. Schedule 10 (Project Schedule) is amended and replaced in its entirety with the corresponding Schedule attached hereto. All references in the Agreement to any such Schedule shall be deemed to refer to the Schedule as updated and amended as stated in this Fourth Amendment.
- 9. Exhibit A-5 of the Agreement is amended to include a new Section 4 as follows (bold/underlining omitted):

#### 4. County Water Wastewater (WWS) Microwave System

Subject to the applicable not-to-exceed amount stated in Exhibit 5.1 ("Microwave System for WWS"), County may acquire as Optional Services any equipment, software, and services that County may deem appropriate to acquire for a microwave system at any County Water and Wastewater (WWS) site(s). Provider may subcontract such goods and services to the extent authorized in writing by the WWS Contract Administrator.

10. <u>Payment Schedules</u>. Section 1 of Exhibit B to the Agreement, System Implementation and Services Fees, is hereby amended as set forth below to align the Payment Schedule, Milestone Payments, Pricing Summary, and allocation of Milestone 3 payments among the Sites with the modifications made to the Schedules. The remainder of Exhibit B is unaffected and remains in full force and effect as originally stated.

# 1. System Implementation and Services Fees

Milestone	Description	% of Original Total System Cost	Approx. % of Amended Total System Cost	Milestone Payment
1	Completion of Contract Design Review (paid)	15%	<del>13%</del> <u>12%</u>	\$4,337,734.95
2	Completion of Factory System Acceptance Testing & Staging (paid)	30%	<del>26%</del> <b>24%</b>	\$8,675,469.90
3	Completion of FNE Installation on a site-by-site basis (radio and microwave) (see breakdown below)	25% on site by site basis	31% 33% on site by site basis	\$10,088,466.05 \$11,785,485.05 (total all sites)
4	Completion of Acceptance Testing & Cutover	15%	15%	\$4,950,358.05 \$5,314,005.05
5	Final System Acceptance (Civil, Radio and Microwave)	15%	15%	\$4,950,358.05 \$5,314,005.05
P25 SYSTI	P25 SYSTEM TOTAL \$33,002,387.00 \$35,426,700.00			

Broward County P25 System Pricing Summary				
P25 Simulcast Equipment Total	\$ 33,508,089			
P25 Simulcast SI Total	\$ 9,494,298			
Sub Total	\$ 43,003,387			
Performance Bond	\$ 250,000			
Additional Features Include:				
OTAR	\$ (no additional cost;			
GPS Locationing (Includes GPS & OTAP)	included in P25 Simulcast			
Enhanced Data	<b>Equipment Total above)</b>			
P1 Integration (ARL) - 10,000 Radios				
System Total:	\$ 43,252,387			
Discounts: (\$10,250,000)				
Fourth Amendment Modifications	\$ 2,424,313			
Increased Broward County Customer Loyalty Discount	\$ (4,250,000)			
Software Licenses	\$ (3,000,000)			
P25 Dynamic Dual Mode TDMA	\$ (1,500,000)			
SmartX and SmartZone Trade In	\$ (1,500,000)			
	\$ <del>33,002,387</del>			
P25 System Total:	<u>\$ 35,426,700</u>			

**P25 System Initial Purchase Order Amount (per Agreement, Section 4.4):** \$39,138,713.57 – The foregoing amount may be comprised of multiple purchase orders to allow the County to allocate support and maintenance funding across multiple years' budgets. The P25 System Initial Purchase Order Amount includes the P25 System Total, Support and Maintenance Services Fees for years 2 through 10, and \$200,000.00 for additional training.

The payment milestone for completion of FNE Installation on a site-by-site basis (radio and microwave) shall be allocated among the Sites as follows:

Site	Estimated	Agreed	Payment per FNE Milestone
	Acceptance Date	Allocation	completion at Site
Core	<del>11/16/18</del> <b>2/22/19</b>	5%	\$565,685.61 <b>\$589,274.25</b>
Coconut Creek	<del>11/28/18</del> <b>2/22/19</b>	<del>5%</del> <u>10%</u>	\$1,131,371.23 <b>\$1,178,548.51</b>
Markham Park	<del>1/8/19</del> <b>3/20/19</b>	5%	\$565,685.61 <b>\$589,274.25</b>
Davie	<del>10/22/18</del> <b>3/29/19</b>	5%	<del>\$565,685.61</del> <b>\$589,274.25</b>
EMS	<del>8/6/18</del> <b>3/20/19</b>	5%	\$565,685.61 <b>\$589,274.25</b>
EOC	N/A	<del>5%</del> <u>0%</u>	\$0
Pompano Beach	<del>1/30/19</del> <b>8/31/19</b>	10%	\$1,131,371.23 <b>\$1,178,548.51</b>
Club			
Points of America	<del>9/20/18</del> <b>3/20/19</b>	5%	\$565,685.61 <b>\$589,274.25</b>
Playa	<del>10/18/18</del> <b>3/20/19</b>	5%	\$565,685.61 <b>\$589,274.25</b>
Miramar	<del>11/8/18</del> <b>3/20/19</b>	5%	<del>\$565,685.61</del> <b>\$589,274.25</b>
Channel 2	<del>1/2/19</del> <b>10/21/19</b>	5%	\$565,685.61 <b>\$589,274.25</b>
Deerfield	<del>1/9/19</del> <b>7/31/19</b>	5%	<del>\$565,685.61</del> <b>\$589,274.25</b>
West Lake Park	<del>2/24/19</del> <b>12/31/19</b>	5%	<del>\$565,685.61</del> <b>\$589,274.25</b>
West Hollywood	<del>2/24/19</del> <b>12/31/19</b>	10%	\$1,131,371.23 <b>\$1,178,548.51</b>
Tamarac	<del>7/12/19</del> <b>8/31/19</b>	5%	\$565,685.61 <b>\$589,274.25</b>
FS 106	<del>12/13/19</del> <b>7/20/19</b>	5%	<del>\$565,685.61</del> <b>\$589,274.25</b>
Parkland	<del>7/10/19</del> <b>8/31/19</b>	10%	\$1,131,371.23 <b>\$1,178,548.52</b>
Total Completion of	of FNE Installation		\$11,313,712.25 <b>\$11,785,485.05</b>
on a site-by-site ba	asis		

11. The Parties agree and stipulate that Motorola Solutions will provide Support and Maintenance Services for both the generators and uninterrupted power supplies inclusive of battery banks (UPS) provided by Motorola Solutions (the "new generators and UPS"), as well as for the existing generators and UPS at certain Sites that will not be replaced as listed below (the "existing generators and UPS"). Support and Maintenance Services for the new generators and UPS commences upon installation of the applicable equipment, and is included in the P25 System Total at no additional cost until one year after Final Acceptance, pursuant to the Agreement and as stated in Exhibit B. Support and Maintenance Services for the existing generators and UPS commences upon the effective date of this Fourth Amendment and shall be invoiced to County quarterly in arrears at the rate of not to exceed \$75,016.00/annually, with an annual escalator of 1.75% commencing upon Final Acceptance. To the extent County elects to modify the additional

equipment included in Support and Maintenance Services pursuant to this paragraph, the Support and Maintenance Services fee will be adjusted accordingly (currently: \$3,104/annually/UPS; \$2,400/annually/generator). The following existing generators and UPS shall be deemed included as part of the "Equipment" included in Support and Maintenance Services under the Agreement and supported by Motorola Solutions:

# **Existing Generators**

Site	Address	Capacity	Manufacturer, Model	SN
Pembroke	3300 SW 52	80 kW	Onan 80DGDA 1 phase 417	39898G
Park	Avenue, Hollywood	Diesel	Amp 120/240 V	
Coconut	5150 Regency Lakes	80 kW	GENERAC 80DGDA	1910419070
Creek	Dr, Coconut Creek	Diesel		
Core	1725 NW 31	80 kW	GENERAC 80DGDA	L900360846
	Avenue, Ft.	Diesel		
	Lauderdale			
Miramar	14401 SW 55	80 kW	Generac 1867170500	2064936
	Street, Miramar	Diesel		
Markham	16001 W. State	80kw Diesel	Generac 1867170500	2064937
Park	Road 84, Sunrise			
EMS	2150 NW 26	180 kW	Generac 3240970100 3phase	2072705
	Avenue, Ft.	Diesel	120/208	
	Lauderdale			
Davie	4501 SW 142	80 kW	Baldor 10J3080G4	P0709050003
	Avenue, Davie	Diesel		

# **Existing UPS**

Site	Address	UPS	Manufacturer, Model	SN
Pembroke	3300 SW 52	(2) 16 KVA / w	APC Symmetra	AD1821120083/
Park	Avenue,	extended runtime		AD1821120082
	Hollywood	cabinet		
Coconut Creek	5150 Regency	(2) 16 KVA / w	APC Symmetra	AD1807120087/
	Lakes Dr,	extended runtime		AD1807120100
	Coconut Creek	cabinet		
Core	1725 NW 31	(2) 16 KVA / w	APC Symmetra	AD1828120004/
	Avenue, Ft.	extended runtime		AD1828120002
	Lauderdale	cabinet		
Miramar	14401 SW 55	(2) 16 KVA / w	APC Symmetra	AD1807120096/
	Street, Miramar	extended runtime		AD1807120079
		cabinet		
Markham Park	16001 W. State	(2) 16 KVA / w	APC Symmetra	AD1811121144/
	Road 84, Sunrise	extended runtime		AD1810120241
		cabinet		
Davie	4501 SW 142	(2)16KVA	Powerware Ferrups	EA266FN004/
	Avenue, Davie		FE18KVA	EA364FN018

Site	Address	UPS	Manufacturer, Model	SN
Tamarac	7515 NW 88th	(1) 15 Kva	Eaton 9166	1024064C0000151127
	Avenue Tamarac			
Points of	2100 S Ocean	(2) 16Kva	Best Ferrups FD18KVA	FD18KO04698/
America	Lane, Ft.			FD18KO04704
	Lauderdale Fl			
Playa Del mar	3900 S Galt	(2) 16KVA	Best Ferrups FD18KVA	FD18KO04706/
	Ocean Dr, Ft			FD18KO04702
	Lauderdale Fl			
Deerfield	300 NE 2nd St	(1) 16Kva	Liebert NX	M13K7H0036
	Deerfield Beach			
EMS	2150 NW 26	(2) 50Kva	Mitsubishi 2033C	05-7M71143EG0001-
	Avenue, Ft.			01/ 05-7M71143
	Lauderdale			EG0001-02

12. Exhibit C is amended at Section 3.A (Equipment Support and Maintenance Services, Equipment Annual Preventative Maintenance) as follows:

# A. Equipment Annual Preventive Maintenance.

Routine maintenance provided by Provider shall include the periodic cleaning, adjusting, calibrating, system diagnostics, and fine tuning of the Equipment; replacement or repair of worn parts; prompt installation of any updates, upgrades, or releases of embedded software or firmware; and component replacement with equal or better equipment with the approval of the Contract Administrator when the component is approaching the end of its useful life. Provider shall perform routine maintenance on at least a monthly basis (or more frequently if appropriate as a result of equipment usage or standards set by the Equipment manufacturer) <u>unless otherwise expressly stated below</u>. Provider shall contact the end user agency at least three (3) business days prior to arrival for the performance of routine maintenance.

\* \* \*

	Standard Preventive Maintenance
Batteries (non-UPS)	
Visual inspection (condition of cells/cabling) – Verify no corrosion, physical connections, dirt/dust, etc.	Х
UPS	
Visual inspection (condition of cells/cabling)'- Verify <u>no</u> corrosion, physical connections, dirt/dust, <u>etc.</u>	Х
For Valve Regulated Lead Acid (VRLA) Batteries: Review battery	<u>X</u>
maintenance logs and make entries into customer logs; Safety	
Checks (Warning/hazard labels; Operational information,	
placards, and labels for operation); provide inspection report	

X (quarterly)
X (annually)
X (quarterly)
X (quarterly)
X (annually)
X (annually)

- 13. Exhibit C to the Agreement is amended in Section 2.A, System Monitoring, to include all generators and UPS (at any Site) within the Monitored Elements Table.
- 14. The County intends to enter into Work Authorization for Optional Services for a Radio Towers Security System in the not-to-exceed amount of One Million Two Hundred Fifty Thousand Dollars (\$1,250,000) plus Support and Maintenance Services ("Security System WA"). The County authorizes its County Administrator to negotiate and execute the Security System WA on behalf of the County. If executed by the Parties, the goods and services provided pursuant the Security System WA will be included as part of Final Acceptance testing and the Final Acceptance Test Plan (Final ATP) for the System, and will be included within the 30 Day Operational Test, unless County Administrator otherwise approves in advance in writing. The Parties authorize Motorola Solutions to subcontract services to ER Tech Systems Group Inc. d/b/a Broadcast Systems in connection with the Radio Towers Security System. The software and equipment provided as part of the Security System WA will be deemed included within the Software and Equipment provided as part of the System, warranted in accordance therewith, and shall be included within the scope of Software and Equipment supported as part of the Support and Maintenance Services at the fees stated in the Security System WA. Any security and access requirements stated in the Security System WA shall be deemed incorporated in the Agreement as if fully set forth herein.

- 15. The effective date of this Fourth Amendment shall be the date of complete execution by both Parties.
- 16. This Fourth Amendment may be executed in counterparts, each of which shall be deemed to be an original, but all of which, taken together, shall constitute one and the same agreement.

(The remainder of this page is blank.)

BROWARD COUNTY through its BOARD OF Mayor or Vice-Mayor, authorized to execute	o have made and executed this Fourth Amendment: COUNTY COMMISSIONERS, signing by and through its e same by Board action on the day of, 2019, by and through its, duly		
BROV	WARD COUNTY		
ATTEST:	BROWARD COUNTY, by and through its Board of County Commissioners		
Broward County Administrator, as ex officio Clerk of the Broward County Board of County Commissioners	Mayor  day of, 2019  Approved as to form by Andrew J. Meyers Broward County Attorney Governmental Center, Suite 423 115 South Andrews Avenue Fort Lauderdale, Florida 33301 Telephone: (954) 357-7600 Telecopier: (954) 357-7641		
	By René D. Harrod (Date) Deputy County Attorney		

RDH 5/23/2019 P25 Fourth Amendment #437461.5

# FOURTH AMENDMENT TO BROWARD COUNTY P25 SYSTEM AND SERVICES MASTER AGREEMENT WITH MOTOROLA SOLUTIONS, INC.

# <u>PROVIDER</u>

WITNESSES:	MOTOROLA SOLUTIONS, INC.
Signature	By Authorized Signor
Print Name of Witness	Print Name and Title
Signature	day of, 2019
Print Name of Witness	
	ATTEST:
	Corporate Secretary or authorized agent
(CORPORATE SEAL)	

# ATTACHMENT A ADDITIONAL EQUIPMENT PROVIDED PURSUANT TO FOURTH AMENDMENT

QTY	NOMENCLATURE	DESCRIPTION	BLOCK	SUB SYS
1	SP1#585938	COCONUT CREEK SPECIAL ORDER TOWER MODIFICATIONS	TOWER	COCONUT CREEK
5	DSAPM7487K248	ADVANCED POWER MONITOR, 740- 870 MHZ, 36-60V DC (INC SINGLE COUPLER)	RSM MONITORING	ALL SITES
22	DSRSM000048	RECEIVE SYSTEMS MONITOR, 36- 60VDC	RSM MONITORING	ALL SITES
3	DSSP74964440DFF1RU	ANT LINE COUPLER 740-960MHZ 40DB 4-PORTS SUIT APM748 AND APM8796	RSM MONITORING	ALL SITES
70	DSSPNFMALC	SIX PACK RF SAMPLE PORT FOR COMBINER LMPS	COMBINER TEST PORTS	ALL SITES
1	DQMWBROW7705RT	18.US.832502 V1 INCLUDES1.01-2.08 7705-SAR-8, SPARES & ADJ	ROUTERS	ALL SITES
1	DQMWBROWNFMPNM	18.US.832502 V1 INCLUDES 3.01- 3.02 NFM-P & ADJ	ROUTERS	ALL SITES
23	DSHPJ9782A	HP PROCURVE 2530-24 SWITCH	ROUTERS	ALL SITES
1	CVN7151	RED HAT 7.X - MULTI CPU AND 4 GUESTS	ROUTERS	ALL SITES
1	DLN7001	HIGH CAPACITY NON REDUNDANT SERVER FRE	ROUTERS	ALL SITES
1	DSP203MONITOR	HP PRODISPLAY P203 20-INCH MONITOR	ROUTERS	ALL SITES
1	DVN4381	SOFTWARE, VMWARE VSPHERE 6.X ENT PLUS 2 CPU SW	ROUTERS	ALL SITES
1	T8126	FORTINET FIREWALL APPLIANCE	ROUTERS	ALL SITES
1	TT3225	Z2 MINI WORKSTATION 258G 8G NON RET	ROUTERS	ALL SITES
10	DSMW3HE05838AA	250W 120/240V AC POWER CONVERTER	ROUTERS	ALL SITES
10	DSMW3HE05837BA	7705 AC POWER CONVERTER PIGTAIL - O-RING	ROUTERS	ALL SITES

Amended Excerpts of SOW A-2 Facilities and Infrastructure Development	

#### 2.1 Site Name: Core

Core is an existing Broward County Radio site. In accordance with Solicitation R1422515P1 Appendix B- Addendum 2, a new 24' X 32' pre- cast shelter will be installed in addition to the existing 24' X 32' shelter. A new DC Power System will be installed in the new shelter, along with a new generator and transfer switch. The existing shelter will utilize the existing UPS and existing generator. The existing tower will be modified to support the antenna loads per the tower structural analysis, as further detailed in Attachment B.



Figure 2-1: Core

#### Site Details:

#### **Site Engineering:**

- Perform National Environmental Policy Act (NEPA) Threshold Screening, including limited literature and records search and brief reporting, as necessary to identify sensitive natural and cultural features referenced in 47 Code of Federal Regulations (CFR) Chapter 1, subsection 1.1307 that may be potentially impacted by the construction activity, and perform all actions necessary to alleviate or remedy that impact.
- Provide a structural engineering analysis for antenna support structure to support the antenna system.
- Provide tower climbing and tower mapping services to collect information about structural members and existing equipment.
- Redesign the compound to add an additional new 24' X 32' shelter and 100KW, 120/240VAC, single phase diesel generator with a 500 gal belly tank.
- Calculate wind loading requirements for the shelter and generator foundations.
- Calculate wind loading requirements for new shelter, including shelter door and new ice bridge.

- Remove 2 Bogner Rx Antennas and their associated TTA's, transmission line, Side Arms and mounts from the top of the tower
- Install five antennas for the RF system to top of tower.
- Supply and install side arm(s) for all antenna and dish mounts.
- Install two tower top amplifiers.
- Install 1/2-inch transmission line as required.
- Install 7/8-inch transmission line as required.
- Install 1-1/4-inch transmission line as required.

- Install three Microwave Dishes.
- Install Elliptical waveguide as required.
- Perform alignment of each of the microwave paths to ensure that the microwave dishes are optimally positioned.
- Perform sweep tests on transmission lines.
- Install 30 ft of new ice bridge between the new shelter and existing tower.
- Supply and install one ground buss bar at the bottom of the antenna support structure for grounding RF cables before they make horizontal transition.

#### Existing Facility Improvement Work:

 Provide all necessary equipment and services necessary to fully cutover users from the old system to the new system

#### **Compound Expansion:**

- Install new 24' X 32' shelter and 100KW, 120/240VAC, single phase diesel generator with a 500 gal belly tank
- Expand Compound 45' 5" X 85' 10" to accommodate space required for new 24' X 32' shelter
- · Add new fence and gates as required
- Install new 100KW Diesel Generator

#### **Existing Tower Improvement Work:**

- Modify tower to support specified antenna loads per the tower structural analysis as further detailed in Attachment B (consisting of tower modification schedule, design loading, pictorial elevation drawings, equipment lists, etc.)
- Provide all material and services necessary to implement the design specified in the attached structural analysis.
- Include all necessary construction cranes to support the installation of all material and services.

Table 2-1: System and Site Improvements

	•			•		
SYSTEM						
Ground Elevati	Ft.)	10				
Site Acquisition			No			
Zoning			No			
A&E Services			Yes			
Latitude			Longitude	9		
26 09 00.0			80 11 16.	0		
Site Owner						
Broward Coun	ty, F	L				
Existing Tower	Ht (	Ft.)	Existing T	ower Type	:	
296			Self-supp	orted tow	er	
SITE IMPROVE	MEN	NTS				
New Compour	nd/Ex	kpansion S	Size			
Width (Ft).		Length (	Ft.)	Clearing	Туре	
85′ 10″		109′ 9″		N/A		
New Ice Bridge Length (Ft.)						
30'						
New Shelter Ty	уре					
Thermobond						
New Shelter W	/idth	(Ft.)	New She	elter Lengt	h (Ft.)	
24 feet			32 feet			
New Fuel Tank	(Ga	l.)	New Fue	el Tank (Ty	pe)	
500			Diesel			
New Generato Switch	r/T	ransfer	New Generator (Type)			
Generac			Generac			
Amps/Volts		Туре	Cable (Ft.)			
400A/120/230	VAC	N/A		N/A		
New Antenna: RF New Ant			tenna: New MW Dish:			
5 2			3			
New RF Lines (	Line	ar Ft.)¹				
Trett Iti Ellies (		-inch	1-1/4-	1-5/8-	Wave	
1/2-inch	7/8	-111011	inch	inch	Guide	

<sup>&</sup>lt;sup>1</sup>Or as required.

#### 2.2 Site Name: Coconut Creek

Coconut Creek is an existing Broward County Radio site. In accordance with Solicitation R1422515P1
Appendix B- Addendum 2, a new 24' X 32' pre- cast shelter will be installed in addition to the existing 24' X 32' shelter. A new DC Power System will be installed in the new Shelter; along with a new generator and transfer switch. The existing shelter will utilize the existing UPS and existing generator. The existing tower will be modified to support the antenna loads per the tower structural analysis, as further detailed in Attachment B.



Figure 2-2: Coconut Creek

#### Site Details:

#### Site Engineering:

- Perform National Environmental Policy Act (NEPA) Threshold Screening, including limited literature and records search and brief reporting, as necessary to identify sensitive natural and cultural features referenced in 47 Code of Federal Regulations (CFR) Chapter 1, subsection 1.1307 that may be potentially impacted by the construction activity.
- Provide a structural engineering analysis for antenna support structure, to support the antenna system.
- Provide tower climbing and tower mapping services to collect information about structural members and existing equipment.
  - Redesign the compound to add an additional new 24' X 32' shelter and 100KW, 120/240VAC, single phase diesel generator with a 500 gal belly tank.
  - Calculate wind loading requirements for the shelter and generator foundations.
  - Calculate wind loading requirements for new shelter, including shelter door and new ice bridge.

- Remove 2 Bogner Rx Antennas and their associated TTA's, transmission line, Side Arms and mounts from the top of the tower.
- Relocate 4 BCR80010 Transmit Antennas to 380' level
- Install eight antennas for the RF Systems to the top of the tower.
- Supply and install side arm(s) for all antenna and dish mounts.
- Install three tower top amplifiers.
- Install 1/2-inch transmission line as required.
- Install 7/8-inch transmission line as required.
- Install 1-1/4-inch transmission line as required.
- Install four Microwave Dishes,
- Install Elliptical waveguide as required.
- Perform alignment of each of the microwave paths to ensure that the microwave dishes are optimally positioned.
- Perform sweep tests on transmission lines.

• Supply and install one ground buss bar at the bottom of the antenna support structure for grounding RF cables before they make horizontal transition.

# **Compound Expansion**

- Modify existing compound to accommodate space required for new 24' X 32' shelter
- Install new 24' X 32' shelter
- Install new 100KW, 120/240VAC, single phase diesel generator with a 500 gal belly tank
- Add new fence and gates as required

# **Existing Facility Improvement Work:**

- Provide all necessary equipment and services necessary to fully cutover users from the old system to the new system
- Replace UPS Systems in existing facility

# **Existing Tower Improvement Work:**

- Modify tower to support specified antenna loads per the tower structural analysis as further detailed in Attachment B (consisting of tower modification schedule, design loading, pictorial elevation drawings, equipment lists, etc.)
- Provide all material and services necessary to implement the design specified in the attached structural analysis.
- <u>Include all necessary construction cranes to support the installation of all material and services.</u>

Table 2-2: System and Site Improvements

SYSTEM								
Ground E	10							
Site Acqui	isition		No					
Zoning			No					
A&E Servi	ices		Yes					
Latitude			Long	gitude	<u>;</u>			
26 18 10			80 1	1 45				
Site Owne	er							
Broward (	County, Fl	L						
Existing T	ower Ht (	Ft.)	Exist	ing T	ower Ty	oe		
400			Self-	supp	orted to	wer		
SITE IMPE	ROVEMEN	ITS						
New Com	pound/E>	cpansion S	ize					
Width (Ft	).	Length (F	Ft.)		Clearin	g Type		
N/A		N/A			N/A			
New Ice Bridge Length (Ft.)								
<del>16 feet</del> <b>95 feet</b>								
New Shelf	ter Type							
Thermobo	ond							
New Shelf	ter Width	(Ft.)	Nev	v She	lter Len	gth (Ft.)		
24			32					
New Fuel	Tank (Ga	l.)	New Fuel Tank (Type)					
500			Diesel Belly Tank					
New Gene Switch	erator / T	ransfer	New Generator (Type)					
Generac			Generac					
New Elect	trical Circ	uits						
Amps/Vol	lts	Туре			Cable (Ft.)			
400/120/	240	N/A			N/A			
New Antenna: RF New TTA			ew Antenna: 「A		New MW Dish:			
8 3					4			
New RF Li	nes (Line	ar Ft.) <sup>2</sup>						
1/2-inch	7/8- inch	1-1/4-in			-5/8- ich	Wave Guide		
1720	1290	2025		320		300		

<sup>&</sup>lt;sup>2</sup> Or as required

#### 2.3 Site Name: Markham Park

Markham Park is an existing Broward County Radio site. In accordance with Solicitation R1422515P1 Appendix B - Addendum 2, a new 24' X 32' pre-cast shelter will be installed, in addition to the existing shelter. A new DC Power System will be installed in the new shelter, along with a new generator and transfer switch. The existing UPS and generator will remain as is. The existing guyed tower will be utilized. Additional gates will be provided.



Figure 2-3: Markham Park

#### Site Details:

#### Site Engineering:

- Perform National Environmental Policy Act (NEPA) Threshold Screening, including limited literature and records search and brief reporting, as necessary to identify sensitive natural and cultural features referenced in 47 Code of Federal Regulations (CFR) Chapter 1, subsection 1.1307 that may be potentially impacted by the construction activity.
- Provide a structural engineering analysis for antenna support structure, to support the antenna system.
- Provide tower climbing and tower mapping services to collect information about structural members and existing equipment.
- Redesign the compound to add an additional new 24' X 32' shelter and 100KW, 120/240VAC, single phase diesel generator with a 500 gal belly tank.
- Calculate wind loading requirements for the shelter and generator foundations.
- Calculate wind loading requirements for new shelter, including shelter door and new ice bridge.

- Remove 2 Bogner Rx Antennas and their associated TTA's, transmission line, Side Arms and mounts from the top of the tower.
- Install five antennas for the RF system to top of tower.
- Supply and install side arm(s) for all antenna and dish mounts.
- Install two tower top amplifiers.
- Install 1/2-inch transmission line as required.
- Install 7/8-inch transmission line as required.
- Install 1-1/4-inch transmission line as required.

- Install three Microwave Dishes.
- Install Elliptical waveguide as required.
- Install 60 ft of new ice bridge between the new shelter and existing tower.
- Perform alignment of each of the microwave paths to ensure that the microwave dishes are optimally positioned.
- Perform sweep tests on transmission lines.
- Supply and install one ground buss bar at the bottom of the antenna support structure for grounding RF cables before they make horizontal transition.

#### **Compound Expansion**

- Expand Compound 60' X 80' to accommodate space required for new 24' X 32' shelter
- Install new 24' X 32' shelter
- Remove existing abandoned equipment shelter and generator.
- Add new fence as required
- Additional sliding and personnel gates for ease of maintenance & access. Includes labor and heavy-duty hardware for rolling gates (as opposed to the standard swing gates).
- Install new 100KW, 120/240VAC, single phase diesel generator with a 500 gal belly tank
- Fabricate steel weight distribution plate and make electrical modifications in order for the existing shelter to receive the new DC Power System.
- Upgrade site grounding to the latest revision of R56
- Provide all necessary equipment and services necessary to fully cutover users from the old system to the new system
- Upgrade shelter and supporting systems to optimal conditions, including the following:
  - Ensure roof is in good condition and free of leaks
  - Repair any damaged flooring or siding to building
  - Seal building to prevent pest entry
  - Service all HVAC units and upgrade or, if necessary, to ensure proper cooling of equipment, replace. (County may elect to replace as part of Optional Services, if the HVAC units are not required to be replaced to ensure proper cooling of equipment.)

Table 2-3: System and Site Improvements

SYSTEM						
Ground Elevation (I	Ft.)		9			
Site Acquisition			N	0		
Zoning			N	0		
A&E Services			Υe	es		
Latitude			Lc	ngitude		
26 08 43.1			80	11 43.8		
Site Owner						
Broward County, Fl						
Existing Tower Ht (I	Ft.)		E>	isting Towe	r Type	
415			G	uyed tower		
SITE IMPROVEMEN	ITS					
New Compound/Ex	pansio	on Size				
Width (Ft).		Length (I	Ft.)		Clearing T	ype
60		80			LIGHT	
New Ice Bridge Len	gth (F	t.)				
15						
New Shelter Type						
Precast						
New Shelter Width (Ft.)				New Shelte	er Length (F	t.)
24				32		
New Fuel Tank (Gal	l.)			New Fuel T	Tank (Type)	
1000			Diesel			
New Generator / Tr	ransfe	r Switch	New Generator (Type)			
175KW			Outdoor			
New Electrical Circu	uits					
Amps/Volts Type					Cable (Ft.)	
400-amp; 120/240- volt, single phase			oui	ound 50		
New Antenna: RF New An			itenna: TTA		New MW Dish:	
5 2					3	
New RF Lines (Linea	ar Ft.) <sup>3</sup>					
/2-inch	7/8-inch			1-1/4-inch	1-5/8- inch	Wave Guide

<sup>&</sup>lt;sup>3</sup> Or as required

#### 2.5 Site Name: Davie

Davie is an existing Broward County Radio site. In accordance with Solicitation R1422515P1 Appendix B-Addendum 2, a new 24' X 32' pre-cast shelter will be installed, in addition to the existing shelter. A new DC Power System will be installed in the new shelter, along with a new generator and transfer switch. The existing UPS and generator will remain as is. The existing guyed tower will be utilized and modified to support the antenna loads per the tower structural analysis, as further detailed in Attachment B.



Figure 2-5: Davie

#### Site Details:

# Site Engineering:

- Perform National Environmental Policy Act (NEPA) Threshold Screening, including limited literature and records search and brief reporting, as necessary to identify sensitive natural and cultural features referenced in 47 Code of Federal Regulations (CFR) Chapter one, subsection 1.1307 that may be potentially impacted by the construction activity.
- Provide a structural engineering analysis for antenna support structure, to support the antenna system.
- Provide tower climbing and tower mapping services to collect information about structural members and existing equipment.
- Redesign the compound to add an additional new 24' X 32' shelter and 100KW, 120/240VAC, single phase diesel generator with a 500 gal belly tank.
- Calculate wind loading requirements for the shelter and generator foundations.
- Calculate wind loading requirements for new shelter, including shelter door and new ice bridge.

- Remove 2 BMR 10 Antennas and their associated Transmission line, TTA's, SA's and mounts.
- Relocate 4 existing BMR10 antennas 10 15 feet down from their current location
- Install six antenna(s) for the RF system.
- Supply and install side arm(s) for all antenna and dish mounts.
- Install three tower top amplifiers.
- Install 1/2-inch transmission line as required.
- Install 7/8-inch transmission line as required.
- Install 1-1/4-inch transmission line as required.
- Install five Microwave Dishes.
- Install Elliptical waveguide as required.
- Perform alignment of each of the microwave paths to ensure that the microwave dishes are optimally positioned.
- Install 15' of Waveguide Bridge (ice bridge)

- Perform sweep tests on transmission lines.
- Supply and install one ground buss bar at the bottom of the antenna support structure for grounding RF cables before they make horizontal transition.

# **Existing Facility Improvement Work:**

- Install one new 100 KW diesel generator and automatic transfer switch.
- Provide all necessary equipment and services necessary to fully cutover users from the old system to the new system

# **Compound Expansion:**

- Expand Compound 30' X 88' 2" to accommodate space required for new 24' X 32' shelter
- Install new 24' X 32' shelter
- Add new fence and gates as required
- Install new 100KW 120/240VAC, single phase diesel generator with a 500 gal belly tank
- Provide and implement landscape plan design that includes arborist study, landscape plan, tree survey and tree mitigation plan

#### **Existing Tower Improvement Work:**

- Modify tower to support specified antenna loads per the tower structural analysis as further detailed in Attachment B (consisting of tower modification schedule, design loading, pictorial elevation drawings, equipment lists, etc.)
- Provide all material and services necessary to implement the design specified in the attached structural analysis.
- Include all necessary construction cranes to support the installation of all material and services.

Table 2-5: System and Site Improvements

SYSTEM							
Ground Elevat	tion (	Ft.)	7				
Site Acquisitio	n		No				
Zoning			No				
A&E Services			Yes				
Latitude			Longitude	9			
26 03 56			80 20 18				
Site Owner							
Broward Cour	nty, F	L					
Existing Towe	r Ht (	Ft.)	Existing T	ower Type	<u> </u>		
315			Self Supp	orted			
SITE IMPROVI	EMEN	NTS					
New Compou	nd/Ex	kpansion S	Size				
Width (Ft).		Length (	Ft.)	Clearing	Туре		
30		88′ 2″		N/A			
New Ice Bridge Length (Ft.)							
15							
New Shelter Type							
Thermobond							
New Shelter V	Vidth	(Ft.)	New She	elter Lengt	h (Ft.)		
24			32				
New Fuel Tan	k (Ga	l.)	New Fue	el Tank (Ty	pe)		
500			Diesel				
New Generato Switch	or /Tr	ansfer	New Generator (Type)				
100KW / 400	A		Outdoor				
New Electrica	l Circ	uits					
Amps/Volts		Туре	Cable (Ft.)				
400/120/240		N/A	N/A				
New Antenna: RF New Ant		tenna: New MW D		/ Dish:			
6 2			5				
New RF Lines	(Line	ar Ft.) <sup>5</sup>					
1/2-inch	1/2-inch 7/8-inch			1-5/8- inch	Wave Guide		
975	975		1200	N/A	660		

#### 2.7 Site Name: Miramar

Miramar is an existing Broward County Radio site. In accordance with Solicitation R1422515P1 Appendix B- Addendum 2, a new 12' X 32' pre-cast shelter with a new DC Power System will be installed in addition to the existing shelter. The existing tower will be used. A new DC Power System will be installed for the new shelter, along with a new generator and transfer switch. The existing generator, automatic transfer switch and UPS will not be decommissioned. The existing tower will be modified to support the antenna loads per the tower structural analysis, as further detailed in Attachment B.



Figure 2-7: Miramar

#### **Site Details**

#### Site Engineering:

- Perform National Environmental Policy Act (NEPA) Threshold Screening, including limited literature and records search and brief reporting, as necessary to identify sensitive natural and cultural features referenced in 47 Code of Federal Regulations (CFR) Chapter 1, subsection 1.1307 that may be potentially impacted by the construction activity.
- Provide a structural engineering analysis for antenna support structure, to support the antenna system.
- Provide tower climbing and tower mapping services to collect information about structural members and existing equipment.
- Redesign the compound to add an additional new 12' X 32' shelter and 100KW, 120/240VAC, single phase diesel generator with a 500 gal belly tank.
- Calculate wind loading requirements for the shelter and generator foundations.
- Calculate wind loading requirements for new shelter, including shelter door and new ice bridge.

- Relocate 2 existing BMR12 Rx Antennas and their associated TTA's, SA's and mounts.
- Install five antennas for the RF system.
- Supply and install side arm(s) for all antenna and dish mounts.
- Install two tower top amplifiers.
- Install 1/2-inch transmission line as required.
- Install 7/8-inch transmission line as required.
- Install 1-1/4-inch transmission line as required.
- Install two Microwave Dishes.
- Install Elliptical waveguide as required.
- Perform alignment of each of the microwave paths to ensure that the microwave dishes are

- optimally positioned.
- Install 25' of Waveguide Bridge (ice bridge)
- Perform sweep tests on transmission lines.
- Supply and install one ground buss bar at the bottom of the antenna support structure for grounding RF cables before they make horizontal transition.

#### **Existing Facility Improvement Work:**

- Install one new 100KW diesel generator and automatic transfer switch.
- Provide all necessary equipment and services necessary to fully cutover users from the old system to the new system
- Replace existing UPS systems

#### **Compound Expansion**

- Expand Compound 5' X 64' 11" to accommodate space required for new 12' X 32' shelter
- Install new 12' X 32' shelter
- Add new fence as required
- Additional sliding and personnel gates requested by Broward County for ease of maintenance & access. Includes labor and heavy-duty hardware for rolling gates (as opposed to the standard swing gates).
- Install new 100KW, 120/240VAC, single phase diesel generator with a 500 gal belly tank

#### **Existing Tower Improvement Work:**

- Modify tower to support specified antenna loads per the tower structural analysis as further detailed in Attachment B (consisting of tower modification schedule, design loading, pictorial elevation drawings, equipment lists, etc.)
- <u>Provide all material and services necessary to implement the design specified in the</u> attached structural analysis.
- <u>Include all necessary construction cranes to support the installation of all material and services.</u>

Table 2-7: System and Site Improvements

01/0==>						
SYSTEM						
Ground Elevation (Ft.)			10			
Site Acquisition			No			
Zoning			No			
A&E Services			Yes			
Latitude			Longitude			
25 57 30.7			80 20 18.5			
Site Owner						
Broward County	y, FL					
Existing Tower I	Ht (Ft.)		Existing To	wer Type		
315			Self-Suppo	orted		
SITE IMPROVEN	<b>MENTS</b>					
New Compound	d/Expa	nsion Size	:			
Width		Length (F	t.)	Clearing Ty	/pe	
60		80		Light		
New Ice Bridge	Length	n (Ft.)				
15						
New Shelter Typ	pe					
Precast						
New Shelter Wi	dth (Ft	:.)	New Shel	ter Length (I	-t.)	
12			32			
New Fuel Tank (	(Gal.)		New Fuel	Tank (Type)		
650			Diesel			
New Generator Switch	/Trans	sfer	New Generator (Type)			
100kw / 00 A			Outdoor			
New Electrical C	Circuits	,				
Amps/Volts Type			Cable (Ft.)			
400-amp - 120		Under	rground 50			
volt, single-ph	usc.			New MW Dish:		
New Antenna: F		New Ante	enna: TTA	New MW [	Dish:	
		New Ante	enna: TTA	New MW [	Dish:	
New Antenna: F	RF	2	enna: TTA		Dish:	
New Antenna: F	RF	2 -t.) <sup>7</sup>	1-1/4- inch		Dish:  Wave Guide	

<sup>&</sup>lt;sup>7</sup>Or as required.

#### 2.10 Site Name: Tamarac

Tamarac is a new Broward County Radio site at the existing Tamarac location. In accordance with Solicitation R1422515P1 Appendix B-Addendum 2, the site will receive a new 24' X 32' precast shelter with a new DC Power System, generator and a new 300' self-supported tower.



Figure 2-10: Tamarac

#### Site Details:

#### Tower Work:

- Construct drilled pier type tower foundations including excavation, rebar, and concrete.
- Erect new 300' self-supporting tower
- Supply and install grounding for the tower base.

#### Antenna and Transmission Line:

- Install five antennas for the RF system.
- Supply and install side arm(s) for all antenna and dish mounts.
- Install one tower-top amplifier.
- Install 1/2-inch transmission line as required.
- Install 7/8-inch transmission line as required.
- Install 1-1/4-inch transmission line as required.
- Install two Microwave Dishes.
- Install Elliptical waveguide as required.
- Perform alignment of each of the microwave paths to ensure that the microwave dishes are optimally positioned.
- Perform sweep tests on transmission lines.
- Perform alignment of each of three microwave paths to ensure that the microwave dishes are optimally positioned.
- Supply and install one ground buss bar at the bottom of the antenna support structure for grounding RF cables before they make horizontal transition.

#### **Compound Work:**

 Expand the site to accommodate building an access walkway between the Sprint and Broward County radio site compounds, including removing trees, building a retaining wall, and additional site grading.

Table 2-10: System and Site Improvements

SYSTEM						
Ground Elevation	10					
Site Acquisition			No			
Zoning			No			
A&E Services			Yes			
Latitude			Longitude			
26 12 43.5			80 16 20.5			
Site Owner						
City of Tamarac						
New Tower Ht (F	t.)		New Tower	r Ту	pe	
300			Self-Suppor	rte	d	
SITE IMPROVEM	ENTS					
New Compound	Expan	sion Size				
Width (Ft).		Length (Ft	:.)	C	learing Typ	e
60		80		L	ight	
New Ice Bridge L	ength	(Ft.)				
15						
New Shelter Type	е					
Custom pre-cast						
New Shelter Wid	New Shelt	ter	Length (Ft.	)		
24			32			
New Fuel Tank (	Gal.)		New Fuel	Tar	nk (Type)	
500			Diesel			
New Generator (	kW)		New Generator (Type)			
100 kw / 400 A			Outdoor			
New Electrical Ci	rcuits					
Amps/Volts		Туре		Cable (Ft.)		
400-amp - 120-240- volt, single-phase			ground 50			
New Antenna: RF New Ante			nna: TTA New MW Dish:			ish:
5 1				2		
New RF Lines (Lir	near Ft	) <sup>10</sup>				
1/2-inch	7/8-i	nch	1-1/4-inch	1	1-5/8- inch	Wave Guide
660	660		1005		N/A	330

<sup>10</sup> Or as required.

# 2.12 Site Name: Sunrise Dispatch

Sunrise Dispatch is an existing dispatch site. Any services or work necessary to be performed at this site to achieve the specifications of the System and meet the other requirements of the Agreement shall be completed by Motorola as part of the scope of services hereunder.



Figure 2-13: Sunrise Dispatch Tower

# **Additional Work:**

- Motorola will provide and install an extreme switch to temporarily connect the Sunrise
   Dispatch Center, Coconut Creek Dispatch, and Pembroke Dispatch Center to the Hosted
   Master Site.
- There are 4 switches in this configuration which will allow the Existing Console Sites connected to the HMS Core to be changed over to an Ethernet Connection utilizing the ATT Network.
- This configuration will also allow the Firenet System to use the ATT Network as a backup network path.

#### 2.13 Site Name: Coconut Creek Dispatch

Coconut Creek Dispatch is an existing dispatch site. Any services or work necessary to be performed at this site to achieve the specifications of the System and meet the other requirements of the Agreement shall be completed by Motorola as part of the scope of services hereunder.



Figure 2-14: Coconut Creek Dispatch

#### **Additional Work:**

- Motorola will provide and install an extreme switch to temporarily connect the Sunrise
   Dispatch Center, Coconut Creek Dispatch, and Pembroke Dispatch Center to the Hosted
   Master Site.
- There are 4 switches in this configuration which will allow the Existing Console Sites connected to the HMS Core to be changed over to an Ethernet Connection utilizing the ATT Network.
- This configuration will also allow the Firenet System to use the ATT Network as a backup network path.

#### 2.14 Site Name: Pembroke Pines Dispatch

Pembroke Pines Dispatch is an existing dispatch site. Any services or work necessary to be

performed at this site to achieve the specifications of the System and meet the other requirements of the Agreement shall be completed by Motorola as part of the scope of services hereunder.



Figure 2-15: Pembroke Pines Dispatch

# **Additional Work:**

- Motorola will provide and install an extreme switch to temporarily connect the Sunrise
   Dispatch Center, Coconut Creek Dispatch, and Pembroke Dispatch Center to the Hosted

   Master Site.
- There are 4 switches in this configuration which will allow the Existing Console Sites connected to the HMS Core to be changed over to an Ethernet Connection utilizing the ATT Network.
- This configuration will also allow the Firenet System to use the ATT Network as a backup network path.

#### 2.15 Site Name: FS 106

Broward County FS 106 is a new Broward County Radio site. In accordance with Solicitation R1422515P1 Appendix B- Addendum 2, the site will receive a new 24' X 32' precast shelter with a new DC Power System, generator and a new 300' self-supported tower. Any services or work necessary to be performed at this site to achieve the specifications of the System and meet the other requirements of the Agreement shall be completed by Motorola as part of the scope of services hereunder.



Figure 2-16: FS 106

#### Site Details:

#### **Engineering Services:**

Provide helicopter evaluation to determine the helicopter communications range

#### Tower Work:

- Implement required FDOT traffic plan during construction of the Alligator Alley Site. Includes rental of barricades as required.
- <u>Install reinforced conduits for required FDOT tower foundation testing. Conduits required to be installed in each caisson and run the entire length of the caissons. Requires a foundation redesign and extra labor and materials.</u>
- Construct drilled pier type tower foundations including excavation, rebar, and concrete
- Erect new 300' self-supported tower.
- Supply and install grounding for the tower base.

#### **Compound Work**


- Establish account with Lee County Electrical Coop (LCEC) and provide temporary electrical service (does not include the recurring electrical fees).
- Provide directional boring to connect electrical source to shelter

- Install 4 antennas for the RF system.
- Supply and install side arm(s) for all antenna and dish mounts.
- Install two tower-top amplifiers.
- Install 1/2-inch transmission line as required.
- Install 7/8-inch transmission line as required.
- Install 1-1/4-inch transmission line as required.
- Install four Microwave Dishes.
- Perform sweep tests on transmission lines.
- Install Elliptical waveguide as required.
- Perform alignment of each of the microwave paths to ensure that the microwave dishes are optimally positioned.
- Perform sweep tests on transmission lines.
- Supply and install 1 ground buss bar at the bottom of the antenna support structure for grounding RF cables before they make horizontal transition.

Table 2-12: System and Site Improvements

SYSTEM							
Ground Elevation (F	t.)		17	17			
Site Acquisition	Site Acquisition						
Zoning			No				
A&E Services			Yes				
Latitude			Longitude	9			
26 08 44.2			80 37 42.	5			
Site Owner							
Broward County							
New Tower Ht (Ft.)			New Tow	er Type			
300			Self-Supp	orted			
SITE IMPROVEMEN	TS						
New Compound/Ex	pansio	n Size					
Width (Ft).		Length (Ft.)		Clearing Typ	e		
60		80		Light			
New Ice Bridge Len	gth (Ft.	)					
15							
New Shelter Type							
Custom pre-cast							
New Shelter Width	(Ft.)		New Shelter Length (Ft.)				
24			32				
New Fuel Tank (Gal	.)		New Fuel Tank (Type)				
500			Diesel				
New Generator (kW	/)		New Generator (Type)				
100 kw / 400 A			Outdoor				
New Electrical Circu	iits						
Amps/Volts		Туре		Cable (Ft.)			
·	400-amp - 120-240- volt, single-phase		d	50	50		
New Antenna: RF	New Antenna		a: TTA	New MW Di	sh:		
4		2		4			
New RF Lines (Linea	ar Ft.) <sup>12</sup>						
1/2-inch	7/8-ir	nch	1-1/4-inch	1-5/8- inch	Wave Guide		
660	660		660	N/A	560		

<sup>&</sup>lt;sup>12</sup> Or as required.



Valmont	<sup>lob:</sup> Quotation 334251-02						
1545 Pidco Drive	Project V-33 x 300'						
	Client Motorola Solutions	Drawn by: SKK	App'd:				
Phone: 574-936-4221	Code: TIA-222-G	Date: 04/06/17	Scale: NTS				
	Path:	norther lake for 11 TO MITCH Suck Principles	Dwg No E-1				

Figure 2-17: FS 106 Tower

#### 2.16 Site Name: Parkland

Parkland is a new Broward County Radio site. In accordance with Solicitation R1422515P1 Appendix B- Addendum 2, the site will receive a new 24' X 32' precast shelter with a new DC Power System, generator and a new 300' self- supported tower




Figure 2-18: Parkland

#### **Site Details:**

# **Tower Work:**

- Construct Drilled Pier tower foundations including excavation, rebar, and concrete
- Erect new 300' self-supported tower.
- Supply and install grounding for the tower base.

# Antenna and Transmission Line:

- Install five antennas for the RF system.
- Supply and install side arm(s) for all antenna and dish mounts.
- Install two tower-top amplifiers.
- Install 1/2-inch transmission line as required.
- Install 7/8-inch transmission line as required.
- Install 1-1/4-inch transmission line as required.
- Install 4 Microwave Dishes.
- Perform sweep tests on transmission lines.
- Install Elliptical waveguide as required.
- Perform alignment of each of the microwave paths to ensure that the microwave dishes are optimally positioned.
- Perform sweep tests on transmission lines.
- Supply and install 1 ground buss bar at the bottom of the antenna support structure for grounding RF cables before they make horizontal transition.


# **Compound Work:**

• Provide an asbestos survey and any necessary remediation, remove of the existing septic tank, demolish an existing onsite building (as designated by County), and provide final grading and sod replacement.

Table 2-13: System and Site Improvements

SYSTEM							
Ground Elevation (Ft.)				17			
Site Acquisition				No			
Zoning				No			
A&E Services				Yes			
Latitude				Longitude			
26 21 17.8				80 16 59.	2		
Site Owner							
Broward County							
New Tower Ht (Ft.)				New Towe	er .	Туре	
300				Self-Suppo	ort	ed	
SITE IMPROVEMEN	TS						
New Compound/Ex	pansio	n Size					
Width (Ft).		Length (Ft.)			(	Clearing Type	е
60		80			L	ight	
New Ice Bridge Len	gth (Ft.	)					
15							
New Shelter Type							
Custom pre-cast							
New Shelter Width	(Ft.)		١	New Shelter Length (Ft.)			
24			3	32			
New Fuel Tank (Gal	.)		ı	New Fuel Tank (Type)			
500			ı	Diesel			
New Generator (kW	/)		١	New Generator (Type)			
100 kw / 400 A			(	Outdoor			
New Electrical Circu	ıits						
Amps/Volts		Туре			(	Cable (Ft.)	
400-amp - 120-240- single-phase	-volt,	Underground	d		5	50	
New Antenna: RF		New Antenn	a:	TTA New MW Dish:		sh:	
5	2			4			
New RF Lines (Linea	ar Ft.) <sup>13</sup>						
1/2-inch	7/8-ir	nch	1	L-1/4-inch		1-5/8- inch	Wave Guide
660	660		ç	915		N/A	630

<sup>&</sup>lt;sup>13</sup> Or as required.



Valmont	<sup>00</sup> Quotation 334251-02						
1545 Pidco Drive	Project V-33 x 300'						
	Client Motorola Solutions	Drawn by: SKK	App'd:				
Phone: 574-936-4221	Code: TIA-222-G	Date: 04/06/17	Scale: NTS				
FAX:	Path:	Dwg No E-1					

# 2.17 Site Name: West Hollywood

West Hollywood is a new Broward County Radio site. In accordance with Solicitation R1422515P1 Appendix B-Addendum 2, the site will receive a new 24' X 32' precast shelter with a new DC Power System, generator and a new 300' selfsupported tower.




Figure 2-19: West Hollywood

#### **Site Details:**

# Additional Engineering / Zoning Support Services

- Zoning support for tower height variance and proximity to local housing
- Platform design to raise Shelter, Generator and its 500 Gal Diesel tank above flood plain
- Tower Work:
- Construct pier and pad type tower foundations including excavation, rebar, and concrete
- Erect new 300' self-supported tower.
- Supply and install grounding for the tower base.

# Additional Compound Work:

- Erect a 6' high platform to raise the 24' X 32' communications shelter and the generator with its 500gal diesel belly tank above the flood plain.
- <u>Develop and implement landscape design plan that includes arborist study, landscape plan, tree survey and tree mitigation plan.</u>
- Provide all necessary work and services to comply with Wetland Mitigation Plan
   Requirement, including the application package, a project narrative, Uniform Mitigation
   Assessment Method (UMAM) documentation, and associated maps and figures. The narrative will include documentation of elimination and reduction of impacts, proposed mitigation, and cumulative impacts based on information provided by County.

# Antenna and Transmission Line:


- Install five antennas for the RF system.
- Supply and install side arm(s) for all antenna and dish mounts.
- Install two tower-top amplifiers.
- Install 1/2-inch transmission line as required.
- Install 7/8-inch transmission line as required.

- Install 1-1/4-inch transmission line as required.
- Install two Microwave Dishes.
- Perform sweep tests on transmission lines.
- Install Elliptical waveguide as required.
- Perform alignment of each of the microwave paths to ensure that the microwave dishes are optimally positioned.
- Perform sweep tests on transmission lines.
- Supply and install 1 ground buss bar at the bottom of the antenna support structure for grounding RF cables before they make horizontal transition.

Table 2-14: System and Site Improvements

SYSTEM							
Ground Elevation (Ft.)				.5			
Site Acquisition		No					
Zoning				No			
A&E Services				Yes			
Latitude				Longitude			
26 03 37.2				80 12 00.	0		
Site Owner							
Broward County							
New Tower Ht (Ft.)				New Towe	er '	Туре	
300				Self-Suppo	ort	ted	
SITE IMPROVEMEN	TS						
New Compound/Ex	pansio	n Size					
Width (Ft).		Length (Ft.)			(	Clearing Type	е
60		80			Light		
New Ice Bridge Leng	gth (Ft.	)					
15							
New Shelter Type							
Custom pre-cast							
New Shelter Width	(Ft.)		١	New Shelter Length (Ft.)			
24			3	32			
New Fuel Tank (Gal	.)		١	New Fuel Tank (Type)			
500			Diesel				
New Generator (kW	/)		١	New Generator (Type)			
100			(	Outdoor			
New Electrical Circu	ıits						
Amps/Volts		Туре			(	Cable (Ft.)	
400-amp; 120/240- single-phase	volt,				Ç	50	
New Antenna: RF		New Antenn	a:	TTA	1	New MW Dis	sh:
5	2			2			
New RF Lines (Linea	ar Ft.) <sup>14</sup>						
1/2-inch	7/8-ir	nch	1	L-1/4-inch		1-5/8- inch	Wave Guide
660	660		9	915		N/A	335

<sup>&</sup>lt;sup>14</sup> Or as required.



Valmont	Ouotation 334251-02					
1545 Pidco Drive	Project V-33 x 300'					
	Client Motorola Solutions	Drawn by: SKK	App'd:			
Phone: 574-936-4221	Code: TIA-222-G	Date: 04/06/17	Scale: NTS			
FAX:	Path:	Dwg No E-1				

# 2.18 Site Name: Pompano Beach Club

Pompano Beach Club is a new Broward County Radio site. In accordance with Solicitation R1422515P1 Appendix B- Addendum 2<sub>7-</sub>-

The 3<sup>rd</sup> floor equipment room will be used. The transmission line and wave guide will be transported to the roof via a cable ladder mounted on the west side of the building, then stuccoes and paint will be used to camouflage the cable ladder so that it blends in with the building view. Antennas and dishes will be mounted on the roof on top of existing roof mounted buildings. The existing building generator will be used, if possible.



Figure 2-20: Pompano Beach Club

A DC power system will be installed into the 3<sup>rd</sup> floor equipment room.

Any services or work necessary to be performed at this site to achieve the specifications of the System and meet the other requirements of the Agreement shall be completed by Motorola as part of the scope of services hereunder.

#### **Site Details**

# Site Engineering:

- Perform National Environmental Policy Act (NEPA) Threshold Screening, including limited literature and records search and brief reporting, as necessary to identify sensitive natural and cultural features referenced in 47 Code of Federal Regulations (CFR) Chapter one, subsection 1.1307 that may be potentially impacted by the construction activity.
- Provide a structural engineering analysis for antenna support structure, to support the antenna system
- Provided a structural analysis for the equipment room floor support for the new DC Power System
- Provided a structural analysis for the cable ladder attachment to the outside west wall

# Antenna and Transmission Line:

- Install five antennas for the RF system.
- Supply and install side arm(s) for all antenna and dish mounts.
- Install two tower top amplifiers.
- Install 1/2-inch transmission line as required.
- Install 7/8-inch transmission line as required.
- Install two Microwave Dishes.
- Install Elliptical waveguide as required.
- Perform alignment of each of the microwave paths to ensure that the microwave dishes are optimally positioned.

- Perform sweep tests on transmission lines.
- Supply and install one ground buss bar at the bottom of the antenna support structure for grounding RF cables before they make horizontal transition.

# **Existing Facility Improvement Work:**

- Fabricate concrete platform to support the new DC Power System batteries.
- Upgrade site grounding to the latest revision of R56
- Provide all necessary equipment and services necessary to fully cutover users from the old system to the new system
- Upgrade equipment and supporting systems to optimal conditions, including the following:
  - Ensure roof is in good condition and free of leaks
  - Repair any damaged flooring or siding to equipment room
  - Seal equipment room to prevent pest entry
  - Service all HVAC units and upgrade and/or replace as necessary to ensure proper cooling of equipment
- X-ray building exterior wall to determine routing of the transmission lines along exterior of building and through a load bearing column.

Table 2-15: System and Site Improvements

SYSTEM						
Ground Elevat	ion (	Ft.)	10			
Site Acquisition			No			
Zoning			No			
A&E Services			Yes			
Latitude			Longitude	2		
26 05 48.0			80 06 26.			
Site Owner						
Pompano Bea	ch Cl	ub South	Tower			
Existing Towe	r Ht (	Ft.)	Existing T	ower Type		
260			Roof Top			
SITE IMPROVI	EME	NTS				
New Compou	nd/Ex	kpansion S	Size			
Width (Ft).		Length (	Ft.)	Clearing	Туре	
N/A		N/A		N/A		
New Ice Bridg	e Len	gth (Ft.)				
N/A						
New Shelter T	ype					
3rd floor equi	pmer	nt room b	uildout			
New Shelter V	Vidth	(Ft.)	New Shelter Length (Ft.)			
N/A			N/A			
New Fuel Tan	k (Ga	l.)	New Fuel Tank (Type)			
N/A			N/A			
New Generato Switch	or /Tr	ansfer	New Generator (Type)			
N/A			N/A			
New Electrica	Circ	uits				
Amps/Volts		Туре		Cable (Ft	:.)	
N/A		N/A		N/A		
New Antenna	w Antenna: RF New An		tenna:	New MW Dish:		
5		2		2		
New RF Lines	(Line	ar Ft.) <sup>15</sup>				
1/2-inch	7/8	-inch	1-1/4- inch	1-5/8- inch	Wave Guide	
400	800		1200	N/A	800	

 $<sup>^{\</sup>rm 15}\,{\rm Or}$  as required.

#### 2.19 Site Name: EMS

EMS is an existing Broward County Radio site. In accordance with Solicitation R1422515P1 Appendix B-Addendum 2, the existing 24' X 32' shelter, tower and generator will be used. A new DC power system will be provided. The existing UPS will be decommissioned and removed. A remote generator connector and manual transfer switch will be added to this site. In addition, an FM200 Fire suppression system will be added to this site. The existing Tower foundation will be evaluated to ensure that the foundation can support the required Antenna loading per the tower structural analysis.



Figure 2-21: EMS

#### Site Details:

#### Site Engineering:

- Perform National Environmental Policy Act (NEPA) Threshold Screening, including limited literature and records search and brief reporting, as necessary to identify sensitive natural and cultural features referenced in 47 Code of Federal Regulations (CFR) Chapter 1, subsection 1.1307 that may be potentially impacted by the construction activity.
- Provide a structural engineering analysis for antenna support structure, to support the antenna system.
- Provide a foundation engineering analysis for foundation to support the antenna support structure.
- Provide tower climbing and tower mapping services to collect information about structural members and existing equipment.
- Decommission antennas, feed lines, and equipment associated with the "backup" system for the existing system.
- Provide an appraisal of the value of current shelter to properly address permit costs.

#### Antenna and Transmission Line:

- Install three antennas for the RF system.
- Supply and install side arm(s) for all antenna and dish mounts.
- Install one tower-top amplifiers.
- Install 1/2-inch transmission line as required.
- Install 7/8-inch transmission line as required.
- Install 1-1/4-inch transmission line as required.
- Install three Microwave Dishes.
- Perform sweep tests on transmission lines.
- Install Elliptical waveguide as required.
- Perform alignment of each of the microwave paths to ensure that the microwave dishes are optimally positioned.
- Supply and install 1 ground buss bar at the bottom of the antenna support structure for grounding RF cables before they make horizontal transition

Table 2-16: System and Site Improvement

SYSTEM							
Ground Elevat	tion (	Ft.)		10	10		
Site Acquisition				No			
Zoning				No			
A&E Services				Yes			
Latitude				Longit	ude		
26 09 14.4				80 10 3	38.3		
Site Owner							
Broward Cour	nty, F	L					
Existing Towe	r Ht (	Ft.)		Existin	g Tower Ty	ре	
400				Guyed	tower		
SITE IMPROVI	EME	NTS					
New Compou	nd/Ex	kpansid	on Siz	ze			
Width (Ft).		Leng	th (Ft	:.)	Clearing	Туре	
N/A		N/A			N/A		
New Ice Bridg	e Len	gth (F	t.)				
N/A							
New Shelter T	ype						
N/A							
New Shelter V	Vidth	(Ft.)		New Shelter Length (Ft.)			
N/A				N/A			
New Fuel Tan	k (Ga	l.)		New Fuel Tank (Type)			
N/A				N/A			
New Generate	or (kV	V)		New Generator (Type)			
N/A				N/A			
New Electrica	l Circ	uits					
Amps/Volts		Туре			Cable (Ft	.)	
N/A		N/A			N/A		
New Antenna	: RF	New TTA	Ante	nna:	New MW	/ Dish:	
3		1			3		
New RF Lines	(Line	ar Ft.)¹	16				
1/2-inch	7/8	-inch	1-1,	/4-inch	1-5/8- inch	Wave Guide	
450	450		900	)	N/A	1500	
-	•		•				

 $<sup>^{\</sup>rm 16}\,\rm Or$  as required.

#### SECTION 3 RESPONSIBILITIES AND ASSUMPTIONS

The following description of responsibilities and assumptions is provided to clarify the parties' respective responsibilities. In the event of a conflict between anything set forth herein and the Specifications or the Final Acceptance Criteria, the Specifications and the Final Acceptance Criteria shall govern the responsibilities of Provider and the requirements for Final Acceptance.

# 3.1 Motorola Solutions Responsibilities

Motorola shall be responsible for the following:

# 3.1.1 Site Engineering for New Sites

- Prepare site construction drawings showing the layout of various new and existing site components.
- Conduct site walks to collect pertinent information from the sites (e.g., location of Telco, power, existing facilities, etc.).
- Perform a boundary and topographic survey for the property on which the communication site is located or will be located.
- Prepare a site exhibit and sketch of the site to communicate to the property owner of the lease space and planned development at the particular site location.
- Prepare record drawings of the site showing the as-built information.
- Perform construction staking around the site to establish reference points for proposed construction.
- Perform NEPA Threshold Screening, including limited literature and records search and brief reporting, as necessary to identify sensitive natural and cultural features referenced in 47 CFR Chapter 1, subsection 1.1307 that may potentially be impacted by the construction activity. This does not include the additional field investigations to document site conditions if it is determined that the communication facility "may have a significant environmental impact" and thus require additional documentation, submittals, or work. Regional Environmental Review (RER) report submittals if required by FEMA have not been included. Perform Cultural Resource study as needed to identify sensitive historical and archaeological monuments that might be impacted by construction.
- Conduct soil boring tests at tower locations and prepare geotechnical report of soil conditions at the location of tower foundations.
- Conduct construction inspection of foundation steel prior to pour, materials testing of concrete and field density tests of backfill to ensure quality construction.
- Check tower erection for plumbness, linearity and alignment after installation.
- Perform inspection of the site and the work performed by the Contractor to document that
  the site is built in accordance with the "Site Plans" and document any deviations or
  violations.
- Prepare, submit and track application for local permit fees (zoning, electrical, building, etc.),
   prepare FAA filings, and procure information necessary for filing.
- Run modifications to the frequency plan for additional intermodulation interference studies.
- Any other required site preparation activities identified in the specifications or not immediately identified as a Broward County responsibility.

# 3.1.2 Site Preparation for New Sites

- Obtain the permits such as electrical, building, and construction permits, and coordinate
  any inspections with local authorities that may be needed to complete site development
  work.
- Where required, provide the services of a Special Inspector, as per requirement of municipality.
- Provide mobilization costs for the construction crews.
- Perform light clearing of brush, grubbing, and disposal of vegetation and shrub growth in the site compound area.
- Grade the site compound and 10-foot path around it to provide a level, solid, undisturbed surface for installation of site components.
- Supply and install gravel surfacing to a depth of six inches, including herbicide treatment
  and geotextile fabric installation within the fenced in site compound area, and a three-foot
  path around it.
- Provide silt fence around the compound to control soil erosion.
- Supply and install eight-foot-high chain-link fencing with gate around the shelter compound.
- Perform site touch-up (fertilize, seed, and straw) disturbed areas not covered with gravel after completion of construction work.
- Secure power connection to the site, associated permitting and installation of a meter and
  disconnect within 50 feet of the shelter location. County will assist with interacting with the
  applicable utilities to the extent reasonably requested by Motorola, but all services shall be
  provided at no cost to County. Demarcation points shall be as determined by the applicable
  utilities.
- Any other required site preparation activities identified in the specifications or not immediately identified as a Broward County responsibility.

# 3.1.3 Site Component Installation for New Sites (New shelter sites are Channel 2, Deerfield, Tamarac, West Lake Park, FS 106, West Hollywood, Parkland, Miramar, Davie, Coconut Creek, Core and Markham Park)

- Construct one reinforced concrete foundation necessary for a 24-foot X 32-foot shelter (all new shelters shall be 24 x 32 except for Miramar which will be 12 X 32.
- Supply and install one prefabricated 24-foot X 32-foot shelter as specified in Section 5.3 Shelters, except Miramar that will be 12-foot X 32-foot. (Note: Motorola Solutions agrees with the county in that falling ice impacting the roof of the shelters will not be an issue. However, Motorola Solutions has chosen to exceed the roof loading in order to comply with the intent of the shelter specs (5.3 Shelters, F. Roof, F). As such, Motorola Solutions has increased the roof load by 50% to 150 psf.).
- Supply and install 500 gallon diesel belly fuel tanks, and attach to the 100KW Generac generators (except for the Deerfield site).
- Supply and install fuel tank monitors on the tanks to monitor low fuel in tanks and run alarm wiring to the building located within 50 feet of the tank.
- Supply and install one single-phase meter pedestal (see individual sites for amperage) and

- hook-up for electrical service by the local utility.
- Provide all trenching, conduit, and cabling necessary for underground hook-up of power to the shelter from nearby utility termination located within 50 cable feet of the shelter.
- Supply and install a perimeter grounding system around the compound, shelter and tower (where applicable). The ground system is to tie to the fence and all new metal structures within the compound to meet current Motorola Solutions' R56 standards.
- Conduct one three-point ground resistance test of the site.
- Supply and install one freestanding 24-inch-wide cable/ice bridge from the tower to the shelter.
- Any other required site preparation activities identified in the specifications or not immediately identified as a Broward County responsibility.

# 3.1.4 Motorola Responsibilities for Existing Sites

- Upgrading existing site grounding systems to the latest revisions of R56, including internal shelter grounding, external shelter grounding, tower grounding, and subterranean grounding
- Reinforce flooring as necessary to support the DC power system
- Evaluate heating and cooling for existing HVAC systems and provide any enhancements necessary
- Evaluate floor loading and upgrade floors if necessary to accommodate the weight of the equipment, including the DC plant
- Ensure a sufficient number of entry ports, and add additional ports if necessary
- Add additional support facilities for the proposed radio network, including but not limited to cable ladders, ice bridge, ground bus bars, etc.
- All applicable environmental and permitting (NEPA, SHPO, building permits, etc.)
- Provide any facility upgrades necessary to support the cutover, including temporary shelters, entry ports, ice bridge, cable ladders, etc.
- Decommission old antennas and feedlines at the conclusion of the project
- Reconfigure site power distribution system for DC
- Upgrade site electrical system in order to comply with NFPA 70, Article 708
- Provide a site structural analysis for each site
- Perform tower mapping to validate existing antenna systems and heights for use in the structural analysis
- Motorola will provide electrical upgrades, with respect to breaker panels and circuit breakers in order to accommodate the new DC power system for the new radio system.
- Perform electrical and heat loading to determine the full impact at each site, and provide the necessary remediation, if required.
- Upgrade shelter and supporting systems to optimal conditions, including the following:
  - o Ensure roof is in good condition and free of leaks
  - Repair any damaged flooring or siding to building
  - Seal building to prevent pest entry
  - Service all HVAC units and upgrade or, if necessary to ensure proper cooling of equipment, replace. (County may elect to replace as part of Optional Services, if the HVAC units are not required to be replaced to ensure proper cooling of equipment.)

• Any other required site preparation activities identified in the specifications or not immediately identified as a Broward County responsibility.

# 3.1.5 Additional Requirements for all Sites (unless otherwise stated)

- Ensure a fully functioning automatic fire suppression system exists at all sites which is fully compliant with NFPA and all other applicable codes.
- Nokia Routers Replacement: Remove Coriant routers and replace with Nokia routers and add
  also add 4 additional routers in order to accommodate ATT connections at the Coconut Creek
  Dispatch, Sunrise Dispatch, Pembroke Pines Dispatch and Motorola Hosted Master Site. The
  addition will also include a Nokia Fault Management server which will monitor the health of
  the network. This addition will better allow Broward County to utilize other networks such as
  FireNet and ATT to route and prioritize traffic.
- Receive System Module Additional for Receive (RX) Monitoring: Install and configure the Receive System Module at all Broward County Radio Frequency (RF) Sites. These modules will allow field personnel to monitor the performance of the Receive Antenna System as well as alarm and log events that are outside normal operating parameters.
- Combiner Test Ports: Install and configure combiner test ports at all Sites. The sample port kit is added to the RF Combining System between the isolator and the isolator load and have a female connector for the sample port. The sample ports allow field personnel to hot tune the combiner during operation which greatly reduces site downtime during service windows.
- Ensure all new shelters have two (2) port entries. Added second waveguide entry port to shelters: Alligator Alley, Deerfield, Tamarac, Parkland, West Hollywood, West Lake Park.
- Develop and implement landscape plan for Hollywood-West, Tamarac, Davie, and West Lake
   Park, and additional Sites as necessary, including tree surveys, an arborist study, and
   landscape plan as well as the determination and implementation of a tree mitigation plan.

   This plan also includes meeting and working with permitting agencies as required.
- Provide a landscape contingency plan for remaining future sites. Includes tree surveys, an arborist study and landscape plan as well as the determination of a tree mitigation plan. This plan also includes meeting and working with permitting agencies, as required.

#### **Broward County Responsibilities**

County shall be responsible for the following:

# 3.1.6 Broward County Responsibilities for Existing Sites

- Pay for the usage costs of power, leased lines, and generator fueling both during the construction/installation effort and on an ongoing basis.
- Pay for application fees, taxes, and recurring payments for ownership of the property.
- Maintain existing access roads in order to provide clear and stable entry to the site for heavy-duty vehicles and cranes. Sufficient space must be available at the site for these vehicles to maneuver under their own power, without assistance from other equipment.
- Arrange for space on the structure for installation of new antennas at the heights on

- designated existing antenna-mounting structures. The towers will meet all applicable EIA/TIA-222 G structural, foundation, ice, wind, and twist and sway requirements.
- Provide any previously procured and currently available as-built structural and foundation drawings of the structure and site location(s) along with geotechnical report(s) if available solely for Motorola reference in conjunction with Motorola Solutions' obligation to conduct a structural analysis and tower mapping at each site.
- Allow use of existing support facilities for the antenna cables (cable ladder, entry ports) from the antenna to the equipment room.

# 3.1.7 Broward County Responsibilities for New Sites

- Review site design drawings within thirty calendar days of submission by Motorola Solutions
  or its subcontractor(s). Should a re-submission be required, the Broward County shall
  review and approve the re-submitted plans within seven calendar days from the date of
  submittal.
- Pay for application fees, taxes, and recurring payments for ownership of the property.
- Provide personnel to observe construction progress and testing of site equipment according to the schedule provided by Motorola Solutions.
- Provide a right of entry letter from the site owner for Motorola Solutions to conduct field investigations.

# 3.1.8 Broward County Responsibilities for All Sites

• All recurring and non-recurring utility costs including, but not limited to, generator fuel (except first fill), electrical, and Telco, will be borne by Broward County or site owner.

# 3.2 Assumptions

The following assumptions were utilized by Provider in estimating the schedule and work required, and are stated here solely for clarification purposes. Failure of any assumption stated in this Section 3.3 shall not diminish or alleviate any obligation of Provider or modify the scope of services or the cost to County of the services required under this Agreement, unless expressly approved by the County in writing.

# 3.2.1 Assumptions for Existing Sites


- No prevailing wage, certified payroll, or mandatory minority workers are required for this work, other than to the extent expressly set forth in the Agreement.
- All site work is assumed to be done during normal business hours as dictated by time zone (Monday thru Friday, 7:30 a.m. to 5:00 p.m.).

# 3.2.2 Assumptions for New Sites

- All site work is assumed to be done during normal business hours as dictated by time zone (Monday thru Friday, 7:30 a.m. to 5:00 p.m.).
- Site will have adequate electrical service for the new shelter and tower. Utility transformer, transformer upgrades, line, or pole extensions have not been included.
- Hazardous materials are not present at the work location prior to commencement of work by Motorola. Testing and removal of pre-existing hazardous materials found during site

- investigations, construction or equipment installation will be the responsibility of the Broward County.
- The schedule is based on a maximum of 30 days will be required for obtaining approved building permits from time of submission. Motorola is responsible for obtaining building permits, and will not hold the County responsible for delays in the permitting process.
- Based on Motorola Solutions' assessments during site walks, no improvements are required for concrete trucks, drill rigs, shelter delivery, and crane access. Therefore, Motorola will be responsible for these upgrades if the determination made during the site walks was incorrect.
- Subsurface conditions for tower design are based on Presumptive Sand soil parameters, as
  defined by EIA/TIA-222-G. Motorola will be responsible for any additional work or
  materials if this assumption is incorrect.
- The new tower locations will pass the FAA hazard study, zoning, FCC, and environmental
  permitting. To the extent any failure is due to design, construction, or any work
  undertaken by Motorola under this Agreement, Motorola will be responsible for rectifying
  any failures.
- Tower and foundation sizing is based on the tower loading requirements as a result of the RF Antenna System design and the Microwave Antenna System design (i.e., dish sizes and locations obtained from paper path studies). If as a result of NEPA studies, any jurisdictional authority should determine that a communications facility "may have a significant environmental impact," the environmental impact studies or field testing and evaluation related to such determination have not been included. A waiver to zoning requirements like setbacks, tower height limitations, etc. required by the Final Design can be obtained.
- The soil resistivity at the site is sufficient to achieve resistance of ten ohms or less.
- Communications site grounding will be designed and installed per Motorola Solutions' Standards and Guidelines for Communications Sites (R56). Motorola will be responsible for any additional work or materials if this assumption is incorrect.
- Underground utilities are not present in the construction area, and as such no relocation will be required.
- Spoils from the tower foundations can and will be transported to a proper facility away from the site by Motorola.

# Attachment B (Excerpted)



DESIGN LOADING							
LOADING CASE	CODE	WIND SPEED AND ICE LOADING					
1	2017 FLORIDA BUILDING CODE AND ANSI/TIA-222-G FOR BROWARD COUNTY, FLORIDA	180 MPH (ULTIMATE 3 SECOND GUST), NO ICE *139 MPH (NOMINAL 3 SECOND GUST), NO ICE					

NUMBER	ELEVATION	CARRIER	MOUNT	ANTENNA INFORMATION	TRANSMISSION LINES
1	398'	BROWARD COUNTY	SIDE ARMS	(2)- SC412HFLDF ANTENNAS (2)- SE4192-SWBP2LDF ANTENNAS	(2)- ½" (2)- 1½"
2	395'	BROWARD COUNTY	LEGS	(2)- 428E83I10T TTAS	(2)- ½"
3	370'	BROWARD	SIDE ARMS	(1)- CC807-11 ANTENNA (1)- SC412HFLDF ANTENNA (1)- SE4192-SWBP2LDF ANTENNA	(2)- 1 ½" (1)- ½"
4	355'	BROWARD COUNTY	SIDE ARMS	(4)- BCR80013 ANTENNAS	(4)- 1 ½"
5	353'	COCONUT CREEK	SIDE ARM	(1)- BCD80010 ANTENNA	(1)- 1 1/4"
6	353'	BROWARD	SIDE ARM	(1)- SC381-HL-PIM ANTENNA	(1)- ⅓"
7	340*	BROWARD	SIDE ARMS	(2)- SC389-HF3LDF ANTENNA	(2)- 1/6"
8	333'	BROWARD	SIDE ARM	(1)- DB420 ANTENNA	(1)- ¾"
9	325'	BROWARD	LEG	(1)- 428E83I01T TTA	(1)-1/2"
10	310'	BROWARD	SIDE ARMS	(2)- CC450-09 ANTENNAS	(2)- 1/8"
11	300'	BROWARD	SIDE ARM	(1)- ANT450FN ANTENNA	(1)- 1/6"
12	300'	BROWARD	LEG	(4)- PMP450i	(4)- CAT5
13	298'	CORAL SPRINGS	SIDE ARM	(1)- BCD80010 ANTENNA W/ TTA	(1)- ½"
14	231'	CORAL SPRINGS	SIDE ARMS	(2)- BCR80013 ANTENNAS	(2)- %"
15	190'	COUNTY	LEG	(1)- PAD6-59B MICROWAVE	(1)- EW63
16	180*	COUNTY	LEG	(1)- HP3-11 MICROWAVE	(1)- CAT6
17	165'	COUNTY	LEG	(1)- PAD6-59B MICROWAVE	(1)- EW63
18	160'	COUNTY	LEG	(1)- HP3-11 MICROWAVE (1)- SB4-W60C MICROWAVE	(1)- CAT6 (1)- EW63
19	155'	COUNTY	LEG	(1)- PAD8-59A MICROWAVE	(1)- EW63
20	145'	COUNTY	LEG	(1)- D8E-3 MICROWAVE W/ RADOME	(1)- EW63
21	135'	CREEK	LEG	(1)- 6-FT HP MICROWAVE	(1)- EW63
22	110'	CREEK	LEG	(1)- 6-FT HP MICROWAVE	(1)- EW63
23	98*	BROWARD	LEG	(1)- 1-FT X 1-FT ANTENNA	(1)- 1/4"

NUMBER	ELEVATION	CARRIER	MOUNT	ANTENNA INFORMATION	TRANSMISSION LINES	
1	398'	BROWARD COUNTY	SIDE ARMS	(2)- SC412HFLDF ANTENNAS (2)- CC807-11 ANTENNAS	(2)- ½" (2)- 1½"	
2	395'	BROWARD COUNTY	LEGS	(2)- 428E83I10T TTAS	(2)-1/2"	
3	370'	BROWARD COUNTY	SIDE ARMS	(3)- CC807-11 ANTENNAS (1)- SC412HFLDF ANTENNA	(3)- 1 ½" (1)- ½"	
4	353'	COCONUT	SIDE ARM	(1)- BCD80010 ANTENNA	(1)- 1 ¼"	
5	353'	BROWARD	SIDE ARM	(1)- SC381-HL-PIM ANTENNA	(1)- 1/6"	
6	340'	BROWARD	SIDE ARMS	(2)- SC389-HF3LDF ANTENNA	(2)- ¾"	
7	333'	BROWARD COUNTY	SIDE ARM	(1)- DB420 ANTENNA	(1)- ¾"	
8	325'	BROWARD COUNTY	LEG	(1)- 428E83I01T TTA	(1)- ½"	
9	310'	BROWARD COUNTY	SIDE ARMS	(2)- CC450-09 ANTENNAS	(2)- ⅓"	
10	300'	BROWARD COUNTY	SIDE ARM	(1)- ANT450FN ANTENNA	(1)- ¾*	
11	300'	BROWARD	LEG	(4)- PMP450i	(4)- CAT5	
12	298'	CORAL SPRINGS	SIDE ARM	(1)- BCD80010 ANTENNA W/ TTA	(1)- ½"	
13	231'	CORAL SPRINGS	SIDE ARMS	(2)- BCR80013 ANTENNAS	(2)- 5/8"	
14	190'	BROWARD	LEG	(1)- PAD6-59B MICROWAVE	(1)- EW63	
15	180'	BROWARD	LEG	(1)- HP3-11 MICROWAVE	(1)- CAT6	
16	165'	BROWARD	LEG	(1)- PAD6-59B MICROWAVE	(1)- EW63	
17	160"	BROWARD	LEG	(1)- HP3-11 MICROWAVE (1)- SB4-W60C MICROWAVE	(1)- CAT6 (1)- EW63	
18	155'	BROWARD	LEG	(1)- PAD8-59A MICROWAVE	(1)- EW63	
19	135'	COCONUT	LEG	(1)- 6-FT HP MICROWAVE	(1)- EW63	
20	110'	COCONUT	LEG	(1)- 6-FT HP MICROWAVE	(1)- EW63	
21	98'	BROWARD	LEG	(1)- 1-FT X 1-FT ANTENNA	(1)-½*	
					No. 56545	12












DETAILS








THIS DRAWING NOT SUITABLE FOR SCALING


S-4











#### **GENERAL NOTES:**

ALL REFERENCES TO OWNER HEREIN SHALL BE CONSTRUED TO MEAN BROWARD COUNTY OR THEIR DESIGNATED REPRESENTATIVE

SUBSURFACE EXPLORATION REPORT FROM PROFESSIONAL ENGINEERING AND INSPECTION COMPANY, INC., DATED 15 NOVEMBER 1991 AND REPORT FEROM FORCE

ALL CONSTRUCTION SHALL BE INSTALLED UNDER THE FULL TIME SUPERVISION OF A QUALIFIED ENGINEER, KNOWLEDGEABLE, AND EXPERIENCED WITH THE PROPOSED FOUNDATION TYPE. FOUNDATION LOADS ARE BASED ON CRITERIA SET FORTH BY TALEIA-222-6 STRUCTURAL STANDARD FOR ANTENNA SUPPORTING STRUCTURES AND ANTENNAS. FOUNDATIONS WITH MODIFICATIONS ARE DESIGNED FOR THE FOLLOWING UNFACTORED LOADS. TOTAL:

COMPRESSION (PER LEG) - 1907 KIPS UPLIFT (PER LEG) - 1670 KIPS SHEAR - 197 KIPS

CONCRETE SHALL BE PLACED AGAINST UNDISTURBED SOIL EXCEPT FOR TOP OF PIER.

ALL WORK PRESENTED ON THESE DRAWINGS MUST BE COMPLETED BY THE CONTRACTOR UNLESS NOTED OTHERWISE. THE CONTRACTOR MUST HAVE CONSIDERABLE EXPERIENCE IN PERFORMANCE OF WORK SIMILAR TO THAT DESCRIBED HERBIN. BY ACCEPTANCE OF THIS ASSIGNMENT, THE CONTRACTOR IS ATTESTING THAT HE DOSE HAVE SUFFICIENT EXPERIENCE AND ABILITY. THAT HE IS NOWLEDGEABLE OF THE WORK TO BE PERFORMED AND THAT HE IS PROPERLY LICENSED AND PROPERLY REGISTERED TO DO THIS WORK IN THE STATE IN WHICH IT IS TO BE PERFORMED.

UNLESS SHOWN OR NOTED OTHERWISE ON THE CONTRACT DRAWINGS OR IN THE SPECIFICATIONS, THE FOLLOWING NOTES SHALL APPLY TO THE MATERIALS LISTED HERINAFTER, AND TO THE PROCEDURES TO BE USED ON THIS PROJECT.

ALL HARDWARE ASSEMBLY MANUFACTURER'S INSTRUCTIONS SHALL BE FOLLOWED EXACTLY AND SHALL SUPERCEDE ANY CONFLICTING NOTES ENCLOSED HEREIN.

IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE THE CONSTRUCTION SEQUENCE TO INSURE THE SAFETY OF THE STRUCTURE AND ITS COMPONENT PARTS DURING ERECTION AND/OR FIELD MODIFICATIONS.

ALL DIMENSIONS, ELEVATIONS, AND EXISTING CONDITIONS SHOWN ON THE DRAWINGS SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO BEGINNING ANY MATERIALS ORDERING, FABRICATION OR CONSTRUCTION WORK ON THIS PROJECT. ANY DISCREPANCIES SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE OWNER AND THE OWNER AND THE OWNER AND SERGIMENET. THE ORSEPRANCIES MUST BE RESOLVED BEFORE THE CONTRACTOR IS TO PROCEED WITH THE WORK IT THE CONTRACT DOCUMENTS ON NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES. OBSERVATION VISITS TO THE SITE BY THE OWNER AND SHAT HE ENGINEER SHALL NOT INCLUDE INSPECTION OF THE PROTECTIVE MEASURES OR THE CONSTRUCTION PROCEDURES.

ALL MATERIALS AND EQUIPMENT FURNISHED SHALL BE NEW AND OF GOOD QUALITY, FREE FROM FAULTS AND DEFECTS AND IN CONFORMANCE WITH THE CONTRACT DOCUMENTS. ANY AND ALL SUBSTITUTIONS MUST BE PROPERLY APPROVED AND AUTHORIZED IN WRITING BY THE OWNER AND ENGINEER PRIOR TO INSTALLATION. THE CONTRACTOR SHALL FURNISH SATISFACTORY EVIDENCE AS TO THE KIND AND QUALITY OF THE MATERIALS AND EQUIPMENT BEING SUBSTITUTED.

ALL BACKFILL SHALL BE THOROUGHLY COMPACTED TO A MINIMUM OF 95% MODIFIED PROCTOR DENSITY.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR INITIATING, MAINTAINING, AND SUPERVISING ALL SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR INSURING THAT THIS PROJECT AND RELATED WORK COMPLIES WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL SAFETY CODES AND REGULATIONS GOVERNING THIS WORK.

THE CONCRETE MIX DESIGN SHALL BE IN ACCORDANCE WITH THE LATEST PROVISIONS OF ACI, AND SHALL BE DESIGNED FOR THE SPECIFIED LOADS IN A FREEZE-THAW CONDITION AND SHALL HAVE A 28 DAY COMPRESSIVE STRENGTH OF 3,000 PSI.

ALL REINFORCING SHALL BE DEFORMED BARS OF THE SIZES SHOWN, CONFORMING TO THE REQUIREMENTS OF ASTM A615 GRADE 60, DETAILED IN ACCORDANCE WITH THE LATEST EDITION OF ACI 315.

REINFORCING CAGES SHALL BE BRACED TO RETAIN PROPER DIMENSIONS DURING HANDLING AND THROUGHOUT PLACEMENT OF CONCRETE.

WELDING IS PROHIBITED ON REINFORCING STEEL AND EMBEDMENTS.

MINIMUM CONCRETE COVER FOR REINFORGEMENT SHALL BE 3 INCHES UNLESS OTHERWISE NOTED. APPROVED SPACERS SHALL BE USED TO INSURE A 3 INCH MINIMUM COVER ON REINFORGEMENT.

CONCRETE COVER FROM TOP OF FOUNDATION TO ENDS OF VERTICAL REINFORCEMENT SHALL NOT EXCEED 3 INCHES NOR BE LESS THAN 2 INCHES.

MAXIMUM SIZE OF AGGREGATE SHALL NOT EXCEED SIZE SUITABLE FOR INSTALLATION METHOD UTILIZED OR ONE-THIRD CLEAR DISTANCE BEHIND OR BETWEEN REINFORCING.

CONCRETE SHALL BE PLACED IN A MANNER THAT WILL PREVENT SEGREGATION OF CONCRETE MATERIALS AND OTHER OCCURRENCES WHICH MAY DECREASE THE STRENGTH OR DURABILITY OF THE FOUNDATION.

EXPOSED EDGES OF CONCRETE SHALL BE CHAMFERED 3/4" x 3/4" MINIMUM.

CONTRACTOR SHALL VERIFY THE LOCATION OF ALL UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.

FOUNDATION AND ANCHOR TOLERANCES:

CONCRETE DIMENSIONS-PLUS OR MINUS 1".

DEPTH OF FOUNDATION - PLUS 3 INCHES OR MINUS 0".

DRILLED FOUNDATION OUT OF PLUMB - 1.0 DEGREE.

PROJECTION OF EMBEDMENTS - PLUS OR MINUS 1/8"

VERTICAL EMBEDMENTS OUT OF PLUMB  $-\frac{1}{2}$  DEGREE.

MAXIMUM DISTANCE FROM CENTERLINE OF ANCHOR BOLTS TO CENTERLINE OF FOUNDATION - OF PIER DIAMETER UP TO A MAXIMUM OF  $2^{\circ}$ .

ANCHOR BOLT CIRCLE DIAMETER - PLUS OR MINUS 1/16".

AFTER ANCHOR BOLTS ARE INSTALLED AND CONCRETE HAS TAKEN ITS INITIAL SET, ANCHOR BOLTS MUST NOT BE MOVED, BENT OR REALIGNED IN ANY MANNER. A NUT LOCKING DEVICE MUST BE INSTALLED ON ALL ANCHOR BOLTS.

NOTE TO CONTRACTOR:

VERIFY LOCATION OF EXISTING ELECTRICAL, UNDERGROUND UTILITIES, AND TOWER GROUNDING RING BEFORE CONSTRUCTION CONSTRUCTION

Ø 0









SCOTT KOMMINISTRATION OF THE SECOND TO SECOND

A.M.

FOUNDATION NOTES

# STRUCTURAL ANALYSIS REPORT COCONUT CREEK SITE

400' SELF-SUPPORTED TOWER BROWARD COUNTY, FLORIDA

Prepared for:
Motorola Solutions

Representing:
BROWARD COUNTY


April 11, 2019 KCI J.O.: 0119XXX



4505 Falls of Neuse Road, Suite 400 Raleigh, North Carolina 27609 (919) 783-9214

# **TABLE OF CONTENTS**

	Executive Summary	. 1
A.	Purpose/Background	. 2
В.	Conditions Investigated	. 2
C.	Applicable Codes and Provisions of Analysis	. 4
D.	Results	. 4
E.	Recommendations	5




#### **EXECUTIVE SUMMARY**


KCI Technologies, Inc. has completed a rigorous structural analysis of the Coconut Creek Tower. Broward County is proposing to alter the appurtenance configuration of the tower.


KCI studied two loading options with a single loading case each. The first loading option consisted of the interim loading condition where many of the antennas are doubled up during transition and the second loading option was for the final loading. The single loading case consisted of the existing and proposed appurtenances with a 180-mph wind speed (ultimate 3-second gust) with no ice and an Exposure Category C, Topographic Category 1, and Risk Category IV per the 2017 Florida Building Code for Broward County, Florida. This analysis assumes that the proposed transmission lines for the P25 antennas shall be placed on the new waveguide ladder in a stacked configuration and those for the Firenet shall be placed in openings on the existing waveguide ladders.

The results of this analysis indicate that some of the structural components of the tower will exceed the nominal loads established by the ANSI/TIA-222-G standard for the proposed appurtenance configuration at the specified loadings. Modifications as contained briefly will alleviate these overloads.



The purpose of this report is to assess the impact of adding antennas and transmission lines to the existing structure, including whether or not structural modifications are required. Any modifications recommended herein are conceptual only. This is not a construction document. This report may not be suitable for bidding and definitely is not a substitute for complete and properly engineered plans/specifications required to accomplish any recommended modifications. KCI Technologies, Inc. assumes no liability for use of this report for any other purpose than that for which it was intended.





# STRUCTURAL ANALYSIS REPORT CORE SITE

300' SELF-SUPPORTED TOWER BROWARD COUNTY, FLORIDA

Prepared for:
KIRMS COMMUNICATIONS

Representing: BROWARD COUNTY 115 S. Andrews Fort Lauderdale, FL 33501

February 28, 2019 KCI J.O.: 011901412B



4505 Falls of Neuse Road, Suite 400 Raleigh, North Carolina 27609-5210 (919) 783-9214

Florida License EB0004898 Eric S. Kohl, FL License No. 56545

# **TABLE OF CONTENTS**

	Executive Summary	1
A.	Purpose/Background	2
B.	Conditions Investigated	2
C.	Applicable Codes and Provisions of Analysis	6
D.	Results	6
E.	Recommendations	10

### **EXECUTIVE SUMMARY**

KCI Technologies, Inc. has completed a rigorous structural analysis of the Core Tower. Broward County is proposing to alter the appurtenance configuration of the tower.

KCI studied three loading options with a single loading case each. The first loading option consisted of the temporary loading condition where many of the antennas are doubled up during transition and a few are relocated temporarily. The second loading case was for the interim loading condition where many of the antennas are doubled up during transition. The third loading case was for the final loading option. The single loading case consisted of the existing and proposed appurtenances with a 180-mph wind speed (ultimate 3-second gust) with no ice and an Exposure Category C, Topographic Category 1, and Risk Category III per the 2017 Florida Building Code for Broward County, Florida. This analysis assumes that the proposed transmission lines shall be mounted on the existing waveguide ladders.

The results of this analysis indicate that with modifications, none of the structural components of the tower will exceed the nominal loads established by the ANSI/TIA-222-G standard for the proposed appurtenance configuration at the specified loadings. Modifications as contained briefly will alleviate these overloads.

This analysis assumes that modifications as described in KCI modification drawings, job no. 02157427A, dated 6 February 2015, have been satisfactorily installed.

Kirms Communication provided a recent tower mapping that included the asbuilt tower modifications for this analysis. Some of the as-built tower modifications in the mapping did not match the modification drawings and post construction inspection completed by KCI in 2004. Where there are discrepancies, KCI used the modifications that provided the least extra//capacity in the final results for this report.

No. 56545

The purpose of this report is to assess the impact of adding antennas and transmission lines to the existing structure, including whether or not structural modifications are required. Any modifications recommended herein are conceptual only. This is not a construction document. This report may not be suitable for bidding and definitely is not a substitute for complete and properly engineered plans/specifications required to accomplish any recommended modifications. KCI Technologies, Inc. assumes no liability for use of this report for any other purpose than that for which it was intended.



Engineering, Geophysics & Geosciences

1455 LINCOLN PARKWAY, SUITE 500 ATLANTA, GEORGIA 30346 PHONE: (770) 379-8590 FAX: (770) 379-8594 WWW.EGSCI.COM

March 7, 2019 *EGSci Project #: 19-1041870* 

# GEOTECHNICAL INVESTIGATION FOR AN EXISTING TOWER SITE

Project: Existing Tower Site – Davie

Location: Davie, Florida

Prepared for:

KCI 4505 Falls of Neuse Road Suite 400 Raleigh, NC 27609

Prepared by:

EGSci Consulting Inc. 1455 Lincoln Parkway Suite 500 Atlanta, GA 30346



Engineering, Geophysics & Geosciences

1455 LINCOLN PARKWAY, SUITE 500 ATLANTA, GEORGIA 30346 PHONE: (770) 379-8590 FAX: (770) 379-8594 WWW.EGSCI.COM

EGSci Project #: 19-1041870

KCI 4505 Falls of Neuse Road Suite 400

Raleigh, NC 27609

Re: Geotechnical Investigation

Site: Davie

March 7, 2019

4501 SW 142<sup>nd</sup> Ave. Davie, FL 33330 Latitude: N26.065556 Longitude: W80.338333

Type of Tower: 300-foot Self-Support

EGSci Consulting Inc. (EGSci) is pleased to submit to KCI this letter report summarizing our limited geotechnical investigation of a telecommunication site (referenced herein as project site) in Broward County, Florida. The objective of the investigation was to conduct a subsurface exploration at the project site to characterize and evaluate the subsurface conditions in support of the tower foundation analysis.

# **PROJECT AND SITE DESCRIPTION**

The project site is located at 4501 SW 142<sup>nd</sup> Avenue in Davie, Broward County, Florida. The project site consists of an existing 300-foot self-support tower and ancillary tower equipment and structures. Figure 1 shows the project site location, as indicated on the U.S. Geological Survey's (USGS) 1994 Cooper City, Florida 7.5-minute topographic quadrangle map.

# **GEOTECHNICAL INVESTIGATION**

The geotechnical investigation was conducted on February 25, 2019 and consisted of one soil test boring located in the general vicinity of the existing communications tower. The boring was positioned in the field based on accessibility and the location of existing infrastructure at the project site.

The soil test boring (B-1) was advanced using a CME 45 drill rig to a termination depth of 70 feet below ground surface (BGS). Groundwater conditions were observed in the borehole during drilling. Soil samples were collected and transported to EGSci's facility for further examination and are discarded thirty days after completion of fieldwork. The approximate soil boring location is shown on Figure 1, and the soil boring log is attached to this report.

## Field and Laboratory Procedures

Standard Penetration Test (SPT) Boring: The SPT boring was performed in accordance with the American Society for Testing and Materials (ASTM) Standard D1586: Standard Test Method for Standard Penetration Test (SPT) and Split-Barrel Sampling of Soils. This sampling technique involves driving a split spoon (split-barrel) sampler into the soil using a 140-pound hammer, free falling 30 inches. The number of hammer blows required to drive the sampler one foot (after an initial seating of six inches) is termed the N-value or penetration resistance. The penetration resistance provides a general indication of soil density and/or consistency. The boring was advanced using mud rotary techniques. A manual safety hammer was utilized for the Standard Penetration Tests at the project site.

Soil Classification: The samples retrieved from the auger cuttings and split spoon sampler were visually examined and classified in general accordance with the guidelines of ASTM D2487: Standard Classification of Soils for Engineering Purposes (Unified Soil Classification System).

# Subsurface Conditions

The subsurface conditions encountered in the boring drilled at the project site are shown in detail on the boring log attached to this report. Soil boundaries indicated have been inferred from the results of non-continuous sampling and observations of drilling resistance, which can typically represent transitions from one soil type to another, rather than exact planes of stratigraphic change. The conditions summarized in a boring log are location-specific and conditions may differ beyond the boring location.

Groundwater was encountered at a depth of 9 feet BGS during drilling. However, seasonal precipitation may affect the groundwater levels at the project site. A groundwater monitoring program would be required to establish long-term groundwater conditions at the project site, which is beyond the scope of this investigation.

# Regional Geology

According to the USGS digital geologic map of the State of Florida, the geology of the project site area is characterized by the Pleistocene Miami Limestone. This geology is generally described as orangish gray to white, sandy, oolitic limestone with scattered fossils and/or orangish gray to white, fossiliferous, sandy limestone with beds of quartz sand.

# GEOTECHNICAL ANALYSIS AND RECOMMENDATIONS

The geotechnical design parameters presented below are to assist in analyzing the existing foundation system. These design values are based on in-situ conditions observed in the soil test borings and evaluation of subsurface samples. The following sections present our general design and construction recommendations.

### **Tower Foundation**

Based on the geotechnical investigation performed by EGSci, a generalized subsurface profile was developed for the conditions encountered at the project site. The recommended geotechnical design parameters for the existing drilled shaft foundations are presented in Table 1. The foundation should be analyzed in accordance with the applicable codes.

Table 1: Recommended Soil Parameters for the Drilled Shaft Tower Foundations (B-1)

Depth		Material Type For Analysis	Angle of Internal	Total Unit Weight	Buoyant Unit	Undrained Shear	Coefficient of	Ultimate Skin Friction for	Net Ultimate Bearing
From	To	Purposes	Friction		Weight	Strength	Passive Pressure	Drilled Shafts	Resistance
(feet)	(feet)		(Degrees)	(pcf)	(pcf)	(psf)		(psf)	(psf)
0	3	Cohesionless	30	115	-	-	3.0	-	-
3	5	Cohesionless	30	115	-	-	3.0	310	-
5	9	Cohesionless	38	125	-	-	4.2	1,690	-
9	18	Cohesionless	38	125	62.6	-	4.2	2,130	-
18	23	Cohesionless	39	125	62.6	-	4.4	2,355	25,000
23	28	Cohesionless	40	130	67.6	-	4.6	2,500	25,000
28	33	Cohesionless	40	130	67.6	-	4.6	2,500	25,000
33	38	Cohesionless	35	125	62.6	-	3.7	1,710	24,000
38	43	Cohesionless	35	125	62.6	-	3.7	1,675	24,000
43	48	Cohesionless	35	125	62.6	-	3.7	1,780	19,000
48	53	Cohesionless	34	120	57.6	-	3.5	1,620	16,000
53	58	Cohesionless	32	115	52.6	-	3.3	1,600	16,000
58	63	Cohesionless	32	115	52.6	-	3.3	1,475	15,000
63	68	Cohesionless	32	115	52.6	-	3.3	1,645	12,000
68	70	Cohesionless	31	110	47.6	-	3.1	1,460	12,000

Skin friction for depths above 3 feet BGS should be neglected.

### Frost Depth

The regional design frost depth at the project site is 0 inches, which is based on values from the Naval Facilities Engineering Command Soil Mechanics Design Manual (NAVFAC DM 7.01), as reported by the Telecommunications Industry Association Structural Standard for Antenna Supporting Structures and Antennas (ANSI/TIA-222-G).

### Seismic Site Class

Based on the subsurface data encountered in our boring, the International Building Code (IBC) Seismic Site Class is Site Class D. The Seismic Site Class is based on average properties of subsurface materials to a depth of 100 feet BGS. Because soil test borings to 100 feet were not performed at this site, it is necessary to estimate the Seismic Site Class based on the boring performed and the regional geology.

# **Construction Inspection**

In general, foundation recommendations contained in this report are contingent upon inspection by a geotechnical engineer or experienced designated inspector at the time of construction on a full-time basis. Inspections should include observations for compliance with recommendations and/or testing (e.g. in-place density tests), as required. Based on the field observations of the geotechnical engineer or inspector, additional recommendations may be required.

Nominal skin friction and bearing resistance values are provided above; the appropriate reduction factors should be applied per applicable design code.

# **QUALIFICATION OF RECOMMENDATIONS**

This report is for the exclusive use of KCI and the designers of the project described herein and is applicable to this project. The conclusions and recommendations have been prepared by the generally accepted standards of Geotechnical Engineering practice in the State of Florida practicing under similar conditions subject to the time limits, and financial and physical constraints applicable to the services. No other warranty is expressed or implied. EGSci is not responsible for the conclusions, opinions and recommendations of others. Any re-use of this document, particularly by third parties, without our express written permission is solely at their own risk.

Environmental services and/or concerns were not included in our scope of work and have not been addressed in this report.

The analysis and recommendations presented in this report are based on the data obtained from the soil borings, exploration and testing program performed at the location shown in Figure 1 and past experience. Soil conditions may differ beyond those at the boring location and are not reflected in this report. If variations in soil conditions become apparent during excavation, the recommendations and conclusions presented herein may need to be re-evaluated based on on-site observations. We recommend that the contractor notify EGSci as soon as possible regarding variations in soil conditions from those presented herein.

If the design or location of the structure presented herein changes, the recommendations and conclusions presented in this report will not be valid. EGSci must review the changes and modify or approve the recommendations and conclusions.

EGSci Consulting Inc. appreciates the opportunity to work with KCI on this project. If you have any questions or require additional information regarding this report, please do not hesitate to contact us.

Very truly yours,

EGSci Consulting Inc.

Shelly Keary, M.Sc.

Project Geotechnical Engineer

Attachments

Site Figures

Key to Soil Classification

Log of Boring


No.55736

STATE OF

ORIO, SO/ONAL ENTIRE

Mike Khalil, M.Sc., P.E. (FL #55736)

Principal Engineer





Source: USGS Topographic Map Cooper City, Florida; Year: 1994

Scale: Not to Scale



Source: Google Earth Imagery

Scale: Not to Scale

Approximate Boring Location



0



4505 Falls of Neuse Road – Suite 400 Raleigh, NC 27609 Geotechnical Investigation

FIGURE 1

SITE: Davie

Site Location Map and Boring Location Plan



Engineering, Geophysics & Geosciences

# NON-DESTRUCTIVE TESTING INVESTIGATION FOR UNKNOWN FOUNDATIONS OF AN EXISTING TOWER SITE

Project: Existing Tower Site Davie

Location: Davie, Florida

EGSci Project #19.1041870

# Prepared For:

KCI Technologies Inc. 4505 Falls of Neuse Road Suite 400 Raleigh, NC 27609

Prepared By:

EGSci Consulting Inc 1455 Lincoln Parkway Suite 500 Atlanta, GA 30346

March 6, 2019





Engineering, Geophysics & Geosciences

March 6, 2019

# **Re: Non-Destructive Testing Investigation for Unknown Foundations**

Davie 4501 SW 142<sup>nd</sup> Avenue Davie, FL 33330 Latitude: N26.06520 Longitude: W80.33867 ASR #1041870

Type of Tower: Self-Support

EGSci Consulting Inc EGSci) is pleased to submit to KCI Technologies Inc. (KCI), this letter report summarizing our investigation of the tower foundation element for the existing tower site Davie located in Davie, Florida (Site).

## **SCOPE OF SERVICES**

As requested by KCI, the objective of this foundation investigation was to utilize non-destructive testing (NDT) methods, physical measurement of the exposed portion of the tower foundation element, limited excavation, and sub-surface probing to determine the following:

- Approximate dimensions of the tower foundations.
- Approximate metal reinforcement (rebar) content of the tower foundations where applicable).

This letter report is provided to summarize the results of the investigation. Results presented in this report are resultant from interpreted field data and EGSci's past experience with similar projects.

#### RESULTS

The following is a summary of the schematic figures used to present the interpreted results of this investigation:

- Figure 1 General layout and orientation of the tower.
- **Figure 2** Interpreted dimensions of the tower foundation elements.
- Figure 3 Approximate rebar content of the tower foundation elements, as determined from interpreted NDT data.

# **Foundation Length**

NDT data collected for total caisson length was generally of poor quality and difficult to process and interpret due to the following:

- Presence of multiple events at various depths in the interpreted NDT data.
- Inconsistent NDT signal characteristics between data collection locations.
- Interpreted NDT events were relatively low amplitude.
- Interpreted NDT signal was relatively 'noisy' possibly due to background noise, subsurface conditions adjacent to the foundations, and/or internal conditions of the foundations.

Due to these factors, there are multiple interpretable events in the NDT data that could be related to the bottom of the caisson. Interpreted events in the NDT data indicate multiple possible approximate total caisson lengths including 21, 28, 31 and 65 feet. Due to this fact, it is recommended that an additional investigation be performed to better determine the total caisson length.

#### Recommendation

If additional information concerning total foundation length is required, the following options are available:

- Parallel Seismic Investigation This NDT methodology requires that a cased boring be installed within 10 feet of the foundation to be tested and to a depth of at least 10 feet past the maximum anticipated depth of the foundation. This type of testing has the potential to directly measure the concrete velocity and provide a more precise measurement of the foundation length. Given the current layout of the Site, it is anticipated that the Northeast and West foundations are accessible for parallel seismic testing.
- Concrete Coring The total length of the caisson may be determined by advancing a small diameter core along the total length of the caisson.

Please see Appendix A for photos of the site and the exposed portion of the tower foundation elements. See the following section entitled 'Limitations of the Report' for important information regarding the nature of the information provided in this report.

# LIMITATIONS OF THE REPORT

The results as presented in this report are based on the interpretation of collected field data and EGSci's experience. EGSci's services are conducted in a manner consistent with that level of care and skill ordinarily exercised by other members of the NDT community currently practicing under similar conditions subject to the time limits, and financial and physical constraints applicable to the services. Due to the nature of NDT, EGSci cannot guarantee the results of any measurements or dimensions that are not physically measured. The purpose of this investigation is to determine the approximate dimensions and rebar content of the existing tower

foundation element(s). The results and interpretations contained in this report are professional opinions. No other representation, expressed or implied, is included or intended. EGSci assumes no liability for any measurements or dimensions that are not physically confirmed or assumptions that are made assuming standard engineering/construction practices.

NDT methods may not detect all targets and interfaces of interest. It is also possible that the interpreted NDT data may reveal subsurface targets or interfaces that without intrusive sampling prior to data interpretation may have been misinterpreted.

The rebar content of the foundation element(s) presented in this report are interpreted from NDT data and measuring the dimensions of the portion of the foundation element(s) located above ground surface. Physical measurements of a foundation element taken above ground surface (i.e. shaft diameter) may not be representative of the foundation dimensions below ground surface. NDT provides data along individual transects or at individual points and does not represent possible variations in the dimensions/rebar content of a foundation element that occur in areas not encountered with these methods during the investigation.

In the case that multiple layers of rebar are present in a tower foundation element, the rebar content data presented in this report will only reflect the shallowest layer of rebar from the surface where the NDT data was collected.

The data presented in this report should be used by a qualified engineer along with available tower and geotechnical information to determine if the interpreted information for the foundation element(s) are reasonable given all factors.

EGSci will not be responsible for any claims, damages, or liability associated with any other party's interpretations of the data or reuse of the data in this report without our express written authorization.

We appreciate the opportunity to work with you on this project. Please e-mail us if you require additional information at information@egsci.com.

Sincerely,

EGSci Consulting Inc

Andrew Johnson Staff Engineer

Shane Hickman, M.Sc.

Sham High

Senior Geophysicist

# **Attachments**

Figure 1 – Site Map

Figure 2 – Interpreted Dimensions of the Tower Foundation Elements

Figure 3 – Interpreted Results for Rebar Content of the Tower Foundation Elements

Appendix A – Site Photos

Appendix B – Report Limitations

# STRUCTURAL ANALYSIS REPORT DAVIE SITE


300' SELF-SUPPORTED TOWER BROWARD COUNTY, FLORIDA

Prepared for:
KIRMS COMMUNICATIONS

Representing:

BROWARD COUNTY 115 S. Andrews Ave Fort Lauderdale, FL 33301

> April 26, 2019 KCI J.O.: 011901412B



4505 Falls of Neuse Road, Suite 400 Raleigh, North Carolina 27609 (919) 783-9214

Florida License EB0004898 Eric S. Kohl, FL License No. 56545

# **TABLE OF CONTENTS**


	Executive Summary	1
A.	Purpose/Background	2
В.	Conditions Investigated	2
C.	Applicable Codes and Provisions of Analysis	5
D.	Results	6
E.	Recommendations	7

# **EXECUTIVE SUMMARY**

KCI Technologies, Inc. has completed a rigorous structural analysis of the Davie Tower. Broward County is proposing to alter the appurtenance configuration of the tower.

KCI studied two loading options with a single loading case each. The first loading option consisted of the interim loading condition where many of the antennas are doubled up during transition and the second loading case was for the final loading. The single loading case consisted of the existing and proposed appurtenances with a 180-mph wind speed (ultimate 3-second gust) with no ice and an Exposure Category C, Topographic Category 1, and Risk Category III per the 2017 Florida Building Code for Broward County, Florida. This analysis assumes that the proposed transmission lines shall be mounted on the existing waveguide ladders. Proposed lines for the P25 antennas shall be divided evenly between the two new waveguide ladders on the South tower face in a stacked configuration two deep and those for the Firenet shall be placed in openings on the existing waveguide ladders.

The results of this analysis indicate that with modifications, none of the structural components of the tower will exceed the nominal loads established by the ANSI/TIA-222-G standard for the proposed appurtenance configuration at the specified loadings. Modifications as contained briefly will alleviate these overloads.



The purpose of this report is to assess the impact of adding antennas and transmission lines to the existing structure, including whether or not structural modifications are required. Any modifications recommended herein are conceptual only. This is not a construction document. This report may not be suitable for bidding and definitely is not a substitute for complete and properly engineered plans/specifications required to accomplish any recommended modifications. KCI Technologies, Inc. assumes no liability for use of this report for any other purpose than that for which it was intended.

## A. PURPOSE/BACKGROUND

Pursuant to the request of Mr. Harry Kirms of Kirms Communications representing Broward County, KCI Technologies, Inc. was retained to conduct a structural analysis of the Davie Tower. Broward County is proposing to alter appurtenances to the tower. Broward County provided the following information:

- Proposed appurtenances V25, dated 31 January 2019.
- Field Information by Kirms Communications dated 7 December 2018.

Note: KCl did not visit the site for this analysis. KCl had completed a tower mapping for a previous analysis.

# **B. CONDITIONS INVESTIGATED**

This 300-ft self-supported tower was designed and manufactured by Pirod, Inc. KCI was unable to obtain the design drawings.

The tower is located at 4501 SW 142<sup>nd</sup> Ave, Davie, Broward County, Florida.

KCI analyzed the tower using tnxTower software by Tower Numerics, Inc.

KCI examined two loading cases with a single loading option each including the existing and proposed appurtenances. This option included the following case:

<b>Loading Case</b>	Code	Wind Speed and Ice Loading
1	2017 Florida Building Code for Broward County, Florida	180 mph (ultimate 3 second gust), No ice *139 mph (nominal 3 second gust), No Ice

<sup>\*-</sup> Conversion based on 2017 Florida Building Code, Section 1609.1.1 Determination of wind loads, Exception 5.

# STRUCTURAL ANALYSIS REPORT

# **MIRAMAR SITE**

# 300' SELF-SUPPORTED TOWER BROWARD COUNTY, FLORIDA

Prepared for:

# KIRMS COMMUNICATIONS

Representing:

**BROWARD COUNTY** 

115 S. Andrews Fort Lauderdale, Florida 33501

> April 23, 2019 KCI J.O.: 011901412D



4505 Falls of Neuse Road, Suite 400 Raleigh, North Carolina 27609 (919) 783-9214

Florida License EB0004898 Eric S. Kohl, FL License No. 56545

# TABLE OF CONTENTS

	Executive Summary	1
A.	Purpose/Background	2
В.	Conditions Investigated	2
C.	Applicable Codes and Provisions of Analysis	5
D.	Results	5
F	Recommendations	7

### **EXECUTIVE SUMMARY**

KCI Technologies, Inc. has completed a rigorous structural analysis of the Miramar Tower. Broward County is proposing to alter the appurtenance configuration of the tower.

KCI studied a single loading case, which consisted of two loading options. The first loading option consisted of the interim loading condition where many of the antennas are doubled up during transition and the second loading case was for the final loading. The single loading case consisted of the existing and proposed appurtenances with a 180-mph wind speed (ultimate 3-second gust) with no ice and an Exposure Category C, Topographic Category 1, and Risk Category IV per the 2017 Florida Building Code for Broward County, Florida. This analysis assumes that the proposed transmission lines shall be mounted on a new waveguide ladder on the South tower face in a back-back configuration such that only half of the new lines are exposed to wind loading.

The results of this analysis indicate that with modifications, none of the structural components of the tower will exceed the nominal loads established by the ANSI/TIA-222-G standard for the proposed appurtenance configuration at the specified loadings. Modifications as contained briefly herein will alleviate the overloads.



The purpose of this report is to assess the impact of adding antennas and transmission lines to the existing structure, including whether or not structural modifications are required. Any modifications recommended herein are conceptual only. This is not a construction document. This report may not be suitable for bidding and definitely is not a substitute for complete and properly engineered plans/specifications required to accomplish any recommended modifications. KCI Technologies, Inc. assumes no liability for use of this report for any other purpose than that for which it was intended.

# A. PURPOSE / BACKGROUND

Pursuant to the request of Mr. Harry Kirms of Kirms Communications representing Broward County, KCI Technologies, Inc. was retained to conduct a structural analysis of the Miramar Tower. Broward County is proposing to alter the appurtenance configuration of the tower. Kirms Communications provided the following information:

- E-mail with proposed appurtenances dated 29 January 2019.
- Kirms Communication Tower mapping drawings with existing appurtenance loading and existing tower modifications, dated 11 December 2018.
- Proposed appurtenances (via Google Docs) downloaded 6 March 2019.

For previous analyses KCI obtained the following:

- Pirod Tower plans, dated 4/7/2002, A117882.
- Geotechnical report by Tierra, project number 6511-10-076, dated 15 March 2010.

Note: For a previous analysis KCI performed a site visit to gather structural and existing appurtenance information and to determine the general condition of the tower.

# **B. CONDITIONS INVESTIGATED**

This 300-ft self-supported tower was designed and manufactured by Pirod, Inc.

The tower is located at 14401 SW 55th Street, Miramar, Broward County, Florida.

KCI analyzed the self-supported tower using tnxTower by Tower Numerics Inc.

KCI examined a single loading case including the existing, proposed and future appurtenances.

<b>Loading Case</b>	Code	Wind Speed and Ice Loading
1	ANSI/TIA-222-G & 2017 Florida Building Code for Broward County, Florida	180 mph (ultimate 3 second gust), No ice *139 mph (nominal 3 second gust), No ice

<sup>\*-</sup> Wind speed per Section 1620.2 of the 2017 Florida Building Code, as required by the Exception of Section 1601.1.

Existing/Proposed Appurtenances (Interim Loading Condition):

Number	Elevation	Carrier	Mount	Antenna Information	Transmission Lines
1	298'	Broward County	4-ft Side Arm	(1)- CC450-09 Omni antenna	(1)- 7/8"
2	298'	Broward County	6-ft Side Arms	(2)- DS7C13PPYU-D Directional antennas	(2)- 7/8"
3	298'	Broward County	2-ft Side Arms	(4)- PMP-450i antennas (Firenet)	(4)- CAT 5e
4	298'	Broward County	Leg	(2)- 428E83I0T TTAs	(2)- 1/2"
5	293'	Broward County	6-ft Side Arms	(3)- DS7C13PPYU-D Directional antennas	(3)- 1 1/4"
6	278'	Broward County	6-ft Side Arms	(2)- BMR12 Omni antennas*	(2)- 7/8"
7	275'	Broward County	Leg	(2)- TTAs *	(2)- 1/2"
8	273'	Broward County	Side Arms	(4)- BCR80013 Omni antennas	(4)- 1 1/4"
9	260'	Broward County	4-ft Side Arms	(3)- CC450-09 Omni antennas	(3)- 7/8"
10	250'	Miramar	Side Arm	(1)- BCR80013 Omni antenna	(1)- 1 1/4"
11	180'	Broward County	Pipe	(1)- HP4-11 Microwave antenna w/ ODU	(1)- CAT 6
12	165'	Broward County	Pipe	(1)- PAD8-W59A Microwave antenna	(1)- EW63
13	160'	Broward County	Pipe	(1)- HP4-11 Microwave antenna w/ ODU	(1)- CAT 6
14	160'	Broward County	Pipe	(1)- PAD8-W59A Microwave antenna	(1)- EW63
15	155'	Broward County	Pipe	(1)- 8-ft Dish antenna w/ radome	(1)- EW63
16	151'	Miramar	Side Arm	(1)- DB589-Y antenna	(1)- 7/8"
17	135'	Broward County	Pipe	(1)- 8-ft Dish antenna w/ radome	(1)- EW63
18	110'	T-Mobile	Sector	(9)- Panel antennas w/ TMAs and Support Equipment	(12)- 7/8" (3)- 1.584" Hybrid & (3)- 9/16"
19	80'	Broward County	Side arm	(1)- Omni antenna	(1)- 1/2"

<sup>\*-</sup> Relocated Omni antennas and TTAs

# Existing/Proposed Appurtenances (Final Loading Condition):

Number	Elevation	Carrier	Mount	Antenna Information	Transmission Lines
1	298'	Broward County	4-ft Side Arm	(1)- CC450-09 Omni antenna	(1)- 7/8"
2	298'	Broward County	6-ft Side Arms	(2)- DS7C13PPYU-D Directional antennas	(2)- 7/8"
3	298'	Broward County	2-ft Side Arms	(4)- PMP-450i antennas (Firenet)	(4)- CAT 5e
4	298'	Broward County	Leg	(2)- 428E83I0T TTAs	(2)- 1/2"
5	293'	Broward County	6-ft Side Arms	(3)- DS7C13PPYU-D Directional antennas	(3)- 1 1/4"
6	273'	Miramar	Side Arm	(1)- BCR80013 Omni antennas	(1)- 7/8"
7	260'	Broward County	4-ft Side Arms	(3)- CC450-09 Omni antennas	(3)- 7/8"
8	250'	Miramar	Side Arm	(1)- BCR80013 Omni antenna	(1)- 1 1/4"
9	180'	Broward County	Pipe	(1)- HP4-11 Microwave antenna w/ ODU	(1)- CAT 6
10	165'	Broward County	Pipe	(1)- PAD8-W59A Microwave antenna	(1)- EW63
11	160'	Broward County	Pipe	(1)- HP4-11 Microwave antenna w/ ODU	(1)- CAT 6
12	160'	Broward County	Pipe	(1)- PAD8-W59A Microwave antenna	(1)- EW63
13	151'	Miramar	Side Arm	(1)- DB589-Y antenna	(1)- 7/8"
14	110'	T-Mobile	Sector	(9)- Panel antennas w/ TMAs and Support Equipment	(12)- 7/8" (3)- 1.584" Hybrid & (3)- 9/16"
15	80'	Broward County	Side arm	(1)- Omni antenna	(1)- 1/2"

# C. APPLICABLE CODES AND PROVISIONS OF ANALYSIS

KCI utilized the following codes and criteria to conduct the structural analysis:

Standard	Title	Date
ANSI/TIA-222-G-2005	Structural Standard for Antenna Supporting Structures and Antennas	August 2005
ANSI/TIA-222-G-1-2007	Structural Standard for Antenna Supporting Structures and Antennas – Addendum 1	April 2007
ANSI/TIA-222-G-2-2009	Structural Standard for Antenna Supporting Structures and Antennas – Addendum 2	December 2009

Nominal Strengths used to evaluate the integrity of the structure were also in accordance with the above standard.

The following assumptions were made in the analysis:

- 1. The tower has been erected and maintained according to the manufacturer's plans and specifications.
- 2. The structural integrity of the tower has not been compromised.
- 3. All connections and fasteners are in accordance with AISC LRFD specifications.
- 4. The proposed transmission lines shall be mounted on a new waveguide ladder on the South tower face in a back-back configuration such that only half of the new lines are exposed to wind loading.
- 5. All information provided by Kirms Communication and Broward County is accurate and correct.

## D. RESULTS

The results of this analysis indicate that with modifications, none of the structural components of the tower will exceed the nominal loads established by the ANSI/TIA-222-G standard for the proposed appurtenance configuration at the specified loadings. Modifications as contained briefly herein will alleviate the overloads.

Results Summary (Interim Loading Condition):

Item	Results	Elevation	% Capacity (Maximum)	Modifications
Legs	Overloaded	270-ft to 290-ft 120-ft to 140-ft 0-ft to 40-ft	120.2	See below
Diagonal Bracing	Overloaded	220-ft to 270-ft 160-ft to 180-ft 80-ft to 120-ft 0-ft to 20-ft	116.7	See below
Horizontal Bracing	O.K.	All	90.8	None
Leg Bolts	Overloaded	0-ft to 40-ft	114.7	See below
Diagonal Bolts	Overloaded	220-ft to 270-ft	116.7	See below

Horizontal Bolts	-	-	-	-
Anchor Bolts	O.K.	0-ft	84.2	None
Foundation	Overloaded	-	140.6	See below

<sup>\*-</sup> Based on information from the Geotechnical Report by Tierra and the Pirod Foundation Plans.

# Results Summary (Final Loading Condition):

Item	Results	Elevation	% Capacity (Maximum)	Modifications
Legs	Overloaded	270-ft to 290-ft 0-ft to 20-ft	111.9	See below
Diagonal Bracing	Overloaded	220-ft to 270-ft 0-ft to 20-ft	109.2	See below
Horizontal Bracing	O.K.	All	96.5	None
Leg Bolts	Overloaded	0-ft to 20-ft	101.7	See below
Diagonal Bolts	Overloaded	220-ft to 270-ft	109.2	See below
Horizontal Bolts	-	-	-	_
Anchor Bolts	O.K.	0-ft	74.9	None
Foundation	Overloaded	-	127.4	See below

<sup>\*-</sup> Based on information from the Geotechnical Report by Tierra and the Pirod Foundation Plans.

The results of this analysis indicate that with modifications, none of the structural components of the tower will exceed the nominal loads established by the ANSI/TIA-222-G standard for the proposed appurtenance configuration at the specified loadings.

Results Summary (Interim Loading Condition) After Modifications Installed:

Item	Results	Elevation	% Capacity (Maximum)	Modifications
Legs	O.K.	All	98.1	See below
Diagonal Bracing	O.K.	All	96.2	See below
Horizontal Bracing	O.K.	All	71.5	None
Leg Bolts	O.K.	All	98.1	See below
Diagonal Bolts	O.K.	All	75.0	None
Horizontal Bolts	-	-	-	-
Anchor Bolts	O.K.	0-ft	85.7	None
Foundation	Overloaded	-	143.7	See below

<sup>\*-</sup> Based on information from the Geotechnical Report by Tierra and the Pirod Foundation Plans.

Results Summary (Final Loading Condition) After Modifications Installed:

Item	Results	Elevation	% Capacity (Maximum)	Modifications
Legs	O.K.	All	89.4	See below
Diagonal Bracing	O.K.	All	85.6	See below
Horizontal Bracing	O.K.	All	65.4	None

Leg Bolts	O.K.	All	85.4	See below
Diagonal Bolts	O.K.	All	65.6	None
Horizontal Bolts	-	-	-	-
Anchor Bolts	O.K.	0-ft	75.1	None
Foundation	O.K.	All	128.7	See below

<sup>\*-</sup> Based on information from the Geotechnical Report by Tierra and the Pirod Foundation Plans.

# E. RECOMMENDATIONS

The results of this analysis indicate that with modifications, none of the structural components of the tower will exceed the nominal loads established by the ANSI/TIA-222-G standard for the proposed appurtenance configuration at the specified loadings. Modifications include the following:

- 1. Reinforce the legs from 20-ft to 40-ft, 100-ft to 140-ft, 180-ft to 220-ft, 240-ft to 260-ft, and 270-ft to 290-ft with bolt on bracing reinforcement.
- 2. Reinforce the diagonal bracing and diagonal bolts by replacing diagonals with larger size angles and/or bolts.
- 3. Reinforce the foundation by adding helical anchors with a grade beam attached to existing foundations.

This analysis assumes that the proposed transmission lines shall be mounted on a new waveguide ladder on the South tower face in a back-back configuration such that only half of the new lines are exposed to wind loading.

# Schedule 10 - Broward County 700MHz System Project Schedule

Task Name  ode  Broward County 700 MHz P25 System Project Schedule	Duration	Start	Finish	Actual Finish
	730 days?	Mon 6/5/17	Wed 4/22/20	NA
Contract	10 days	Mon 6/5/17	Fri 6/16/17	Fri 6/16/17
Contract Design Review	52 days	Mon 6/19/17	Wed 8/30/17	Wed 8/30/17
Order Processing	58 days	Thu 8/31/17	Tue 11/21/17	Tue 11/21/17
Microwave Manufacturing	83 days	Thu 8/31/17	Tue 1/2/18	Tue 1/2/18
CCSi FNE System Staging	15 days	Wed 11/22/17	Thu 12/14/17	Thu 12/14/17
Ship FNE Equipment to Approved Warehouse in Broward County	199.5 days	Fri 12/15/17	Tue 9/25/18	Tue 9/25/18
Aviat Microwave Staging	188.5 days	Wed 1/3/18	Mon 9/24/18	Mon 9/24/18
Engineering	693 days	Mon 6/5/17	Mon 3/2/20	NA
Additional Task not in original Schedule	397 days	Mon 6/5/17	Wed 12/26/18	NA
DISPATCH CENTER INSTALLATIONS	47 days	Tue 4/30/19	Mon 7/8/19	NA
Remote Sites	595.5 days	Mon 6/5/17	Wed 10/9/19	NA
EMS SITE DEVELOPMENT ETES	428 days	Mon 8/28/17	Mon 5/6/19	NA
Site Civil Work Substantial Completion	0 days	Mon 4/22/19	Mon 5/6/19	NA
DAVIE SITE DEVELOPMENT Master ETNS	432 days	Mon 8/28/17	Fri 5/10/19	NA
Site Civil Work Substantial Completion	0 days	Fri 6/7/19	Fri 6/7/19	NA
POINTS OF AMERICA SITE DEVELOPMENT	462.5 days	Mon 8/28/17	Tue 6/25/19	NA
Site Civil Work Substantial Completion	2 days	Fri 6/7/19	Tue 6/11/19	NA
PLAYA SITE DEVELOPMENT	444 days	Mon 8/28/17	Wed 5/29/19	NA
Site Civil Work Substantial Completion	2 days	Fri 6/7/19	Tue 6/11/19	NA
COCONUT CREEK SITE DEVELOPMENT ETNS	476 days	Mon 8/28/17	Mon 7/15/19	NA
Site Civil Work Substantial Completion	0 days	Wed 4/17/19	Wed 5/1/19	NA
MIRAMAR SITE DEVELOPMENT ETNS	431 days	Mon 8/28/17	Thu 5/9/19	NA
Site Civil Work Substantial Completion	4 days	Fri 6/7/19	Thu 6/13/19	NA
CORE SITE DEVELOPMENT ETNS	434 days	Mon 8/28/17	Tue 5/14/19	NA
	Contract Design Review Order Processing Microwave Manufacturing CCSi FNE System Staging Ship FNE Equipment to Approved Warehouse in Broward County Aviat Microwave Staging Engineering Additional Task not in original Schedule DISPATCH CENTER INSTALLATIONS Remote Sites EMS SITE DEVELOPMENT ETES Site Civil Work Substantial Completion DAVIE SITE DEVELOPMENT Master ETNS Site Civil Work Substantial Completion POINTS OF AMERICA SITE DEVELOPMENT Site Civil Work Substantial Completion PLAYA SITE DEVELOPMENT Site Civil Work Substantial Completion COCONUT CREEK SITE DEVELOPMENT ETNS Site Civil Work Substantial Completion MIRAMAR SITE DEVELOPMENT ETNS Site Civil Work Substantial Completion	Contract Design Review  Order Processing  Sa days  Microwave Manufacturing  CCSi FNE System Staging  Ship FNE Equipment to Approved Warehouse in Broward County Aviat Microwave Staging  Engineering  Additional Task not in original Schedule  DISPATCH CENTER INSTALLATIONS  Remote Sites  EMS SITE DEVELOPMENT ETES  Site Civil Work Substantial Completion  DAVIE SITE DEVELOPMENT Master ETNS  Site Civil Work Substantial Completion  O days  POINTS OF AMERICA SITE DEVELOPMENT  Site Civil Work Substantial Completion  PLAYA SITE DEVELOPMENT  Site Civil Work Substantial Completion  O days  COCONUT CREEK SITE DEVELOPMENT ETNS  Site Civil Work Substantial Completion  O days  COCONUT CREEK SITE DEVELOPMENT ETNS  Site Civil Work Substantial Completion  O days  MIRAMAR SITE DEVELOPMENT ETNS  431 days  Site Civil Work Substantial Completion  4 days	Contract Design Review  Order Processing  Sa days  Thu 8/31/17  Microwave Manufacturing  Ship FNE System Staging  Ship FNE Equipment to Approved Warehouse in Broward County  Aviat Microwave Staging  Engineering  Additional Task not in original Schedule  Browerd County  Additional Task not in original Schedule  Site Civil Work Substantial Completion  DAVIE SITE DEVELOPMENT  Site Civil Work Substantial Completion  POINTS OF AMERICA SITE DEVELOPMENT  Site Civil Work Substantial Completion  PLAYA SITE DEVELOPMENT  Site Civil Work Substantial Completion  PLAYA SITE DEVELOPMENT  Site Civil Work Substantial Completion  PLAYA SITE DEVELOPMENT  Site Civil Work Substantial Completion  COCONUT CREEK SITE DEVELOPMENT ETNS  Site Civil Work Substantial Completion  O days  Fri 6/7/19  COCONUT CREEK SITE DEVELOPMENT ETNS  Site Civil Work Substantial Completion  O days  Fri 6/7/19  MIRAMAR SITE DEVELOPMENT ETNS  431 days  Mon 8/28/17  Site Civil Work Substantial Completion  O days  Fri 6/7/19  MIRAMAR SITE DEVELOPMENT ETNS  A11 days  Mon 8/28/17  Site Civil Work Substantial Completion  O days  Fri 6/7/19  MIRAMAR SITE DEVELOPMENT ETNS  A11 days  Mon 8/28/17  Site Civil Work Substantial Completion  O days  Fri 6/7/19	Contract Design Review         52 days         Mon 6/19/17         Wed 8/30/17           Order Processing         58 days         Thu 8/31/17         Tue 11/21/17           Microwave Manufacturing         83 days         Thu 8/31/17         Tue 11/21/18           CCSi FNE System Staging         15 days         Wed 11/22/17         Thu 12/14/17           Ship FNE Equipment to Approved Warehouse in Broward County         199.5 days         Fri 12/15/17         Tue 9/25/18           Aviat Microwave Staging         188.5 days         Wed 1/3/18         Mon 9/24/18           Engineering         693 days         Mon 6/5/17         Mon 3/2/20           Additional Task not in original Schedule         397 days         Mon 6/5/17         Wed 12/26/18           DISPATCH CENTER INSTALLATIONS         47 days         Tue 4/30/19         Mon 7/8/19           Remote Sites         595.5 days         Mon 6/5/17         Wed 10/9/19           EMS SITE DEVELOPMENT ETES         428 days         Mon 8/28/17         Mon 5/6/19           Site Civil Work Substantial Completion         0 days         Mon 8/28/17         Fri 5/10/19           POINTS OF AMERICA SITE DEVELOPMENT         462.5 days         Mon 8/28/17         Tue 6/25/19           Site Civil Work Substantial Completion         2 days         Fri 6/7/19

0	Task Mode	Task Name	Duration	Start	Finish	Actual Finish
THE STATE OF THE S	<b>-</b> >	Site Civil Work Substantial Completion	0 days	Thu 5/2/19	Thu 5/2/19	NA
	<b>-</b>	MARKHAM PARK SITE DEVELOPMENT ETNS	425 days	Mon 8/28/17	Wed 5/1/19	NA
<b>III</b>	<b>-</b> >	Site Civil Work Substantial Completion	0 days	Thu 4/18/19	Wed 5/1/19	NA
	<b>→</b>	FS106 SITE DEVELOPMENT NTNS	519 days	Mon 6/5/17	Thu 6/20/19	NA
	<b>→</b>	Site Civil Work Substantial Completion	0 days	Wed 5/29/19	Wed 5/29/19	NA
	3	Channel 2	519 days	Mon 8/28/17	Fri 9/13/19	NA
<b>V</b>	<u> </u>	SITE ENGINEERING	16 days	Mon 8/28/17	Tue 9/19/17	Tue 9/19/17
<b>V</b>	<u> </u>	Site visit with AMEC FW	2 days	Mon 8/28/17	Tue 8/29/17	Tue 8/29/17
<b>✓</b>	<b>-</b> >	Prepare site sketch/site layout	9 days	Wed 8/30/17	Tue 9/12/17	Tue 9/12/17
<b>✓</b>	<b>→</b>	Broward County Review and approval of site sketch	5 days	Wed 9/13/17	Tue 9/19/17	Tue 9/19/17
	<b>→</b>	PERMITTING DOCUMENTATION AND FINAL DRAWINGS	448.5 days	Mon 8/28/17	Wed 6/5/19	NA
<b>V</b>	<b>→</b>	Site Survey and mapping	7 days	Mon 8/28/17	Wed 9/6/17	Wed 9/6/17
<b>V</b>	<b>→</b>	FAA application (7460-1) and approval	40 days	Thu 9/7/17	Wed 11/1/17	Wed 11/1/17
<b>V</b>	<b>→</b>	Review Shelter Drawings based on Port Entry Orientation	2 days	Wed 9/20/17	Thu 9/21/17	Thu 9/21/17
<b>V</b>	<b>→</b>	Prepared Construction Drawings of new site	25 days	Wed 9/20/17	Tue 10/24/17	Tue 10/24/17
<b>V</b>	<b>→</b>	Construction Drawings Review and Approval	134 days	Wed 10/25/17	Tue 5/8/18	Tue 5/8/18
<b>V</b>	<b>→</b>	Microwave Path Study & report	10 days	Thu 9/7/17	Wed 9/20/17	Wed 9/20/17
<b>V</b>	<b>→</b>	Tower Design and drawings	15 days	Thu 9/21/17	Wed 10/11/17	Wed 10/11/17
<b>V</b>	<u> </u>	Site Agreement Approved by Site Owner	144 days	Thu 10/12/17	Wed 5/9/18	Wed 5/9/18
<b>V</b>	<u>→</u>	Broward County Site Release/Construction NTP to Motorola	1 day	Wed 3/6/19	Wed 3/6/19	Wed 3/6/19
<b>V</b>	<b>→</b>	Geotechnical testing and report	15 days	Fri 5/11/18	Fri 6/1/18	Fri 6/1/18
<b>V</b>	<b>→</b>	Tower Foundation Design	5 days	Mon 6/4/18	Fri 6/8/18	Fri 6/8/18
<b>V</b>	<u> </u>	Place Order for New Shelter	1 day	Wed 3/6/19	Wed 3/6/19	Wed 3/6/19
<b>V</b>	<b>-</b> >	Shelter Manufacturing	0 days	Fri 11/30/18	Fri 11/30/18	Fri 11/30/18
Ħ	<b>→</b>	Manufacture New Shelter	45 days	Thu 3/7/19	Mon 6/3/19	NA
	■	Mode Mode Mode Mode Mode Mode Mode Mode	Mode  Site Civil Work Substantial Completion  MARKHAM PARK SITE DEVELOPMENT ETNS  Site Civil Work Substantial Completion  FS106 SITE DEVELOPMENT NTNS  Site Civil Work Substantial Completion  Channel 2  SITE ENGINEERING  Site visit with AMEC FW  Prepare site sketch/site layout  Broward County Review and approval of site sketch  PERMITTING DOCUMENTATION AND FINAL DRAWINGS  Site Survey and mapping  FAA application (7460-1) and approval  Review Shelter Drawings based on Port Entry Orientation  Prepared Construction Drawings of new site  Construction Drawings Review and Approval  Microwave Path Study & report  Tower Design and drawings  Site Agreement Approved by Site Owner  Broward County Site Release/Construction NTP to Motorola  Geotechnical testing and report  Tower Foundation Design  Place Order for New Shelter  Shelter Manufacturing	Mode Site Civil Work Substantial Completion  MARKHAM PARK SITE DEVELOPMENT ETNS Site Civil Work Substantial Completion  Site Civil Work Substantial Completion  O days  F\$106 SITE DEVELOPMENT NTNS 519 days Site Civil Work Substantial Completion  O days  Channel 2  Site Civil Work Substantial Completion  O days  Channel 2  Site Site Visit with AMEC FW Site visit with AMEC FW Prepare site sketch/site layout  Forward County Review and approval of site sketch  PERMITTING DOCUMENTATION AND FINAL DRAWINGS Site Survey and mapping  Adays  FAA application (7460-1) and approval  Review Shelter Drawings based on Port Entry Orientation  Prepared Construction Drawings of new site  Construction Drawings Review and Approval  Microwave Path Study & report  Odays  Site Agreement Approved by Site Owner  144 days  Broward County Site Release/Construction NTP to Motorola  Geotechnical testing and report  15 days  Place Order for New Shelter  1 day  Shelter Manufacturing  O days	Mode  Site Civil Work Substantial Completion  MARKHAM PARK SITE DEVELOPMENT ETNS  Site Civil Work Substantial Completion  O days  Thu 4/18/19  FS106 SITE DEVELOPMENT NTNS  Site Civil Work Substantial Completion  O days  Mon 6/5/17  Site Civil Work Substantial Completion  O days  Wed 5/29/19  Channel 2  SITE ENGINEERING  Site visit with AMEC FW  Site visit with AMEC FW  Prepare site sketch/site layout  FS408 Wed 8/30/17  Broward County Review and approval of site sketch  PERMITTING DOCUMENTATION AND FINAL DRAWINGS  Site Survey and mapping  FAA application (7/460-1) and approval  Review Shelter Drawings based on Port Entry  Review Shelter Drawings fo new site  Construction Drawings Review and Approval  Microwave Path Study & report  Microwave Path Study & report  Tower Design and drawings  Site Auryen Stays  Mon 8/28/17  Tower Design and drawings  Site Owner  144 days  Thu 9/7/17  Tower Design and drawings  Site Auryen Stays  Mon 8/28/17  Broward County Site Release/Construction  NTP to Motorola  Geotechnical testing and report  15 days  Fri 5/11/18  Tower Foundation Design  Flace Order for New Shelter  1 day  Wed 3/6/19  Fri 11/30/18	Mode         Site Civil Work Substantial Completion         0 days         Thu 5/2/19         Thu 5/2/19           MARKHAM PARK SITE DEVELOPMENT ETNS         425 days         Mon 8/28/17         Wed 5/1/19           Image: Site Civil Work Substantial Completion         0 days         Thu 4/18/19         Wed 5/1/19           FS106 SITE DEVELOPMENT NTNS         519 days         Mon 6/5/17         Thu 6/20/19           Site Civil Work Substantial Completion         0 days         Wed 5/29/19         Wed 5/29/19           Channel 2         519 days         Mon 8/28/17         Fir 9/13/19           SITE ENGINEERING         16 days         Mon 8/28/17         Tue 9/19/17           Site visit with AMEC FW         2 days         Mon 8/28/17         Tue 9/19/17           Prepare site sketch/site layout         9 days         Wed 8/30/17         Tue 9/19/17           Prepare site sketch/site layout         9 days         Wed 9/3/17         Tue 9/19/17           Prepared County Review and approval of site sketch         5 days         Wed 9/3/17         Tue 9/19/17           PERMITTING DOCUMENTATION AND FINAL DRAWINGS         448.5 days         Mon 8/28/17         Wed 9/6/17         Wed 9/6/17           PA application (7460-1) and approval of yellower         40 days         7 hu 9/7/17         Wed 9/6/17         Wed 9/6/

					_	_	
ID	470	Task Mode	Task Name	Duration	Start	Finish	Actual Finish
821		<b>→</b>	Ship Shelter to Site	2 days	Mon 6/3/19	Wed 6/5/19	NA
822	<b>V</b>	<b>→</b>	Order DC Power Systems	2 days	Fri 5/11/18	Mon 5/14/18	Mon 5/14/18
823	<b>V</b>	<b>-</b> >	Receive Rectifier Rack at Project Warehouse	40 days	Mon 3/4/19	Fri 4/26/19	Fri 4/26/19
824		<b>→</b>	Construction Permits	59 days	Thu 3/7/19	Wed 5/29/19	NA
825	<b>V</b>	<b>→</b>	·	11 days	Thu 3/7/19	Thu 3/21/19	Thu 3/21/19
826		<b>→</b>	· ·	20 days	Fri 3/22/19	Wed 5/29/19	NA
827		<u></u>		0 days	Wed 5/29/19	Wed 5/29/19	NA
828		<b>→</b>	CONSTRUCTION PHASE	40 days	Thu 4/11/19	Fri 6/7/19	NA
829	<b>V</b>	<b>-</b> >		0 days	Thu 4/11/19	Thu 4/11/19	Thu 4/11/19
830		<b>→</b>	Mobilization	1 day	Thu 5/30/19	Thu 5/30/19	NA
831		<u>→</u>	Locate existing utilities	1 day	Fri 5/31/19	Fri 5/31/19	NA
832		<u> </u>	Light clearing and grubbing	1 day	Mon 6/3/19	Mon 6/3/19	NA
833		<b>→</b>	Remove old MDFR Shelter	4 days	Tue 6/4/19	Fri 6/7/19	NA
834		<b>-</b>	Compound grading and silt fencing	4 days	Thu 5/30/19	Tue 6/4/19	NA
835		<b>→</b>	Construction Staking	1 day	Wed 6/5/19	Wed 6/5/19	NA
836		<b>→</b>	SITE COMPONENTS INSTALLATION	43 days	Thu 6/6/19	Tue 8/6/19	NA
837		<b>→</b>		3 days	Thu 6/6/19	Mon 6/10/19	NA
838		⇒	foundations	2 days	Tue 6/11/19	Wed 6/12/19	NA
839		<b>→</b>	testing	2 days	Thu 6/13/19	Fri 6/14/19	NA
840		<b>-</b> >		1 day	Mon 6/17/19	Mon 6/17/19	NA
841		<del>-</del> >		5 days	Tue 6/18/19	Mon 6/24/19	NA
842		⇒	Trench and Install underground power conduits	-	Tue 6/25/19	Thu 6/27/19	NA
843		<b>→</b>		3 days	Fri 6/28/19	Tue 7/2/19	NA
844		<b>-</b> >	Grounding Inspection	0.5 days	Wed 7/3/19	Wed 7/3/19	NA

ID	Task Mode	Task Name	Duration	Start	Finish	Actual Finish
845	<b>→</b>	Conduit inspection and backfill	0.5 days	Wed 7/3/19	Wed 7/3/19	NA
846	<b>→</b>	Offload and Install generator	2 days	Fri 7/5/19	Mon 7/8/19	NA
847	->	Pick up meter panel and Install meter board	2 days	Fri 6/28/19	Mon 7/1/19	NA
848	<b>→</b>	Utility hookup to the site by Electric Co.	15 days	Wed 7/17/19	Tue 8/6/19	NA
849	<del>-</del> >	Cabling and hook up power system to shelter, ATS, generator	5 days	Tue 7/9/19	Mon 7/15/19	NA
850	->	Building/Electrical inspection	1 day	Tue 7/16/19	Tue 7/16/19	NA
851	<b>→</b>	Install ice bridge from shelter to the tower	3 days	Wed 7/3/19	Mon 7/8/19	NA
852	->	EXISTING FACILITY IMPROVEMENTS	0.5 days	Wed 7/17/19	Wed 7/17/19	NA
853	→	Deliver DC Rectifier Rack to Ch2 Site	0.5 days	Wed 7/17/19	Wed 7/17/19	NA
854	3	Antenna and Line Installation	7 days	Tue 9/3/19	Wed 9/11/19	NA
855	→	Ship antennas, line and accessories to the site	1 day	Tue 9/3/19	Tue 9/3/19	NA
856	→	Install antennas, microwave dishes and lines	6 days	Wed 9/4/19	Wed 9/11/19	NA
857	<b>→</b>	SITE EQUIPMENT INSTALLATION	18 days	Wed 8/7/19	Fri 8/30/19	NA
858	-	Ship equipment to site	1 day	Wed 8/7/19	Wed 8/7/19	NA
859	->	Microwave equipment installation	2 days	Thu 8/8/19	Fri 8/9/19	NA
860	<b>→</b>	FNE Equipment installation	10 days	Thu 8/8/19	Wed 8/21/19	NA
861	<b>→</b>	FNE Equipment program & configure	5 days	Thu 8/22/19	Wed 8/28/19	NA
862	⇒	Site Equipment test and baseline	2 days	Thu 8/29/19	Fri 8/30/19	NA
863	->	SITE RESTORATION	48 days	Tue 7/9/19	Fri 9/13/19	NA
864	<b>→</b>	Finish Grade and gravel compound	2 days	Thu 9/12/19	Fri 9/13/19	NA
865	-5	Fencing of tower compound	3 days	Tue 7/9/19	Thu 7/11/19	NA
866	<b>→</b>	Complete grounding connections	2 days	Fri 7/12/19	Mon 7/15/19	NA
867	<b>→</b>	Site touchup and restoration	2 days	Tue 7/16/19	Wed 7/17/19	NA
868	3	FINAL TESTING	36 days	Wed 7/17/19	Thu 9/5/19	NA

ID	0	Task Mode	Task Name	Duration	Start	Finish	Actual Finish
869	111	<b>→</b>	Order & Battery Strings Received at Ch2 Site	30 days	Wed 7/17/19	Tue 8/27/19	NA
870		<b>→</b>	Install DC Power System	3 days	Wed 8/28/19	Fri 8/30/19	NA
871		<b>→</b>	AC connections to DC Power System	2 days	Tue 9/3/19	Wed 9/4/19	NA
872		⇒	DC Power System Startup and Test	1 day	Thu 9/5/19	Thu 9/5/19	NA
873		<b>→</b>	Generator Startup and Test	1 day	Mon 8/12/19	Mon 8/12/19	NA
874		<b>→</b>	Test Fire Suppression System	1 day	Wed 8/7/19	Wed 8/7/19	NA
875		<del>-</del> >	Site Civil Work Substantial Completion	0 days	Wed 8/7/19	Wed 8/7/19	NA
876		<b>→</b>	DEERFIELD SITE DEVELOPMENT NTNS	484 days	Mon 8/28/17	Thu 7/25/19	NA
972		<del>-</del> >	Site Civil Work Substantial Completion	0 days	Fri 7/5/19	Fri 7/5/19	NA
973		<b>→</b>	POMPANO BEACH CLUB SITE DEVELOPMENT	497 days	Mon 8/28/17	Tue 8/13/19	NA
1021		<del>-</del> >	Site Civil Work Substantial Completion	0 days	Thu 8/8/19	Thu 8/8/19	NA
1022		<b>→</b>	WEST LAKE PARK SITE DEVELOPMENT NTNS	536.5 days	Mon 8/28/17	Wed 10/9/19	NA
1110		<b>→</b>	WEST HOLLYWOOD SITE DEVELOPMENT NTNS	518.5 days	Mon 8/28/17	Fri 9/13/19	NA
1207		<b>→</b>	PARKLAND SITE DEVELOPMENT NTNS	200 days	Mon 10/29/18	Thu 8/15/19	NA
1304		→	TAMARAC SITE DEVELOPMENT NTNS	273.5 days	Wed 8/15/18	Fri 9/13/19	NA
1391		<b>→</b>	Site Civil Work Substantial Completion	0 days	Tue 4/30/19	Tue 4/30/19	NA
1392		<b>→</b>	P25 DISPATCH CENTER CONNECTIVITY	38 days	Tue 4/2/19	Thu 5/23/19	NA
1403		<b>→</b>	P25 DISPATCH CENTER CONNECTIVITY	38 days	Tue 4/2/19	Thu 5/23/19	NA
1414		<b>→</b>	Microwave Commissioning	124.5 days	Wed 5/1/19	Fri 10/25/19	NA
1415		<b>→</b>	Microwave Commissioning (1st Wave)	16 days	Thu 5/30/19	Thu 6/20/19	NA
1422		<b>-&gt;</b>	Microwave Commissioning (2nd Wave)	18 days	Fri 9/13/19	Wed 10/9/19	NA
1432		<b>→</b>	Microwave Commissioning (Coconut Creek)	124.5 days	Wed 5/1/19	Fri 10/25/19	NA
1437		<b>→</b>	All Microwave Hops Commissioned	0 days	Fri 10/25/19	Fri 10/25/19	NA
1438		<b>3</b>	MOBILE COMMUNICATIONS TRAILER	40 days	Wed 5/1/19	Wed 6/26/19	NA
1439		<b>→</b>	Antenna Installation Design	20 days	Wed 5/1/19	Wed 5/29/19	NA

						_	
ID	0	Task Mode	Task Name	Duration	Start	Finish	Actual Finish
1440		<b>→</b>	Equipment Installation Design	20 days	Thu 5/30/19	Wed 6/26/19	NA
1441		<b>→</b>	Ship equipment to trailer	1 day	Wed 5/1/19	Wed 5/1/19	NA
1442		<b>→</b>	FNE Equipment installation	10 days	Thu 5/2/19	Wed 5/15/19	NA
1443		<b>→</b>	FNE Equipment program & configure	5 days	Thu 5/16/19	Wed 5/22/19	NA
1444		<u> </u>	Trailer Equipment test and baseline	5 days	Thu 5/23/19	Thu 5/30/19	NA
1445	Ш	<del>-</del> >	Broward County Site Audit	7 days	Fri 5/31/19	Mon 6/10/19	NA
1446		<del>-</del> >	Broward County Trailer Approved	0 days	Mon 6/10/19	Mon 6/10/19	NA
1447		<b>→</b>	SYSTEM OPTIMIZATION	105.5 days	Wed 5/29/19	Fri 10/25/19	NA
1448		<b>→</b>	Master Site, Prime Site and Remote Sites Optimizatio	10 days	Wed 10/9/19	Wed 10/23/19	NA
1449		<b>→</b>	Optimization of Dispatch Consoles	5 days	Wed 5/29/19	Tue 6/4/19	NA
1450		<b>→</b>	System Ready for ATP and CATP Testing	0 days	Fri 10/25/19	Fri 10/25/19	NA
1451		*	ACCEPTANCE TESTING	145 days?	Mon 6/3/19	Mon 12/30/19	NA
1452		*	System ATP's	145 days?	Mon 6/3/19	Mon 12/30/19	NA
1473		<b>→</b>	TECHNICAL TRAINING CLASS	20 days	Wed 12/4/19	Mon 1/6/20	NA
1475		*	CUTOVER	38 days	Thu 1/2/20	Sat 2/22/20	NA
1476		3	Cutover Public Safety Users	37 days	Thu 1/2/20	Sat 2/22/20	NA
1477		<b>→</b>	FINALIZE	687 days	Mon 6/5/17	Sat 2/22/20	NA